

DESIGN		
INT.	DATE	REASON

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
95	•	JASPER	545	16
STA. TO STA.				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
*15,61Y,RS-2,6BR-7				
CONTRACT NO. 94437				

PLOTS & CHECKS		
INT.	DATE	REASON

PAVEMENT SCHEDULE #1

LOCATION	PROCESSING MODIFIED SOIL 12"	LIME	AGGREGATE BASE COURSE, TYPE B 8"	BITUMINOUS MATERIALS (PRIME COAT)	BITUMINOUS MATERIALS (COVER AND SEAL COAT)	COVER COAT AGGREGATE	SEAL COAT AGGREGATE	TEMPORARY RAMP	PORTLAND CEMENT CONCRETE PAVEMENT 7"	BRIDGE APPROACH PAVEMENT	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	AGGREGATE SHOULDERS, TYPE B	AGGREGATE SHOULDERS, TYPE B 6"	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	CONCRETE MEDIAN SURFACE, 4"
	SO. YD.	TON	SO. YD.	GALLON	GALLON	TON	TON	SO. YD.	SO. YD.	SO. YD.	SO. YD.	TON	SO. YD.	FOOT	FOOT	FOOT	SO. FT.
<b>SUBTOTAL</b>	10,766	252	3,369	818	2,442	35	68	80	1,373	278	56	64	57,460	9,406	41	43	361
<b>T.R. 181 (1150N)</b>																	
STA. 116+50 TO STA. 120+00			702	168	503	7.0	14.0										
STA. 120+00 TO STA. 122+09.28			269	69	206	2.9	5.7										
<b>T.R. 92 (700E)</b>																	
STA. 127+50 TO STA. 130+00			532	129	384	5.5	10.8										
STA. 130+00 TO STA. 131+78.89			258	66	196	2.8	5.5										
<b>T.R. 102 (775E)</b>																	
STA. 138+36.12 TO STA. 140+00			284	67	200	2.8	5.6										
STA. 140+00 TO STA. 141+78.68			276	71	212	3.0	5.9										
<b>T.R. 120 (850E)</b>																	
STA. 148+34.45 TO STA. 150+00			227	57	171	2.5	4.9										
STA. 150+00 TO STA. 151+79.71			300	78	233	3.3	6.5										
<b>T.R. 201 (1000N)</b>																	
STA. 156+00 TO STA. 160+00	1,268	29						14					261				
STA. 160+00 TO STA. 170+60.48	3,258	74											699				
<b>BOGOTA ROAD (900E)</b>																	
STA. 166+50 TO STA. 170+00	1,722	39						14					223				
STA. 170+00 TO STA. 175+61.57	1,707	39											356				
CORNER ISLAND															6	22	37
<b>ILLINOIS DRIVE</b>																	
STA. 179+31.41 TO STA. 180+00								13									
<b>TOTALS</b>	18,721	433	6,217	1,523	4,547	65	127	121	1,373	278	56	64	58,999	9,406	47	65	398

PROPOSED SIGN LOCATION SCHEDULE

LOCATION	SIGN MESSAGE	TYPE	SIGN PANEL - TYPE 1 SQ FT	TELESCOPING SIGN SUPPORT - FOOT	STEEL SIGN SUPPORT - FOOT	SIZE	POST TYPE
<b>CIPS ROAD</b>							
STA. 85+00, RT.	STOP AHEAD	W3-1	9		15	36"X36"	TELESCOPING
STA. 89+50, RT.	STOP	R1-1	9		15	36"X36"	TELESCOPING
CORNER ISLAND	STOP	R1-1	9		15	36"X36"	TELESCOPING
STA. 90+50, LT.	STOP	R1-1	9		15	36"X36"	TELESCOPING
STA. 95+00, LT.	STOP AHEAD	W3-1	9		15	36"X36"	TELESCOPING
<b>BOGOTA ROAD</b>							
STA. 165+00, RT.	STOP AHEAD	W3-1	9		15	36"X36"	TELESCOPING
STA. 169+50, RT.	STOP	R1-1	9		15	36"X36"	TELESCOPING
CORNER ISLAND	STOP	R1-1	9		15	36"X36"	TELESCOPING
STA. 170+50, LT.	STOP	R1-1	9		15	36"X36"	TELESCOPING
STA. 175+00, LT.	STOP AHEAD	W3-1	9		15	36"X36"	TELESCOPING
<b>TOTAL</b>			90		150		

CHECKS		
INT.	DATE	REASON

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
 FAP ROUTE 95 (IL RTE. 33)  
 SECTION (5,6)Y,RS-2,6BR-7  
 JASPER COUNTY

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_  
 DATE: 09/16/02

DRAWN BY: BISHOP  
 DESIGNED BY: COLBROOK  
 CHECKED BY: COLBROOK

**COMPUTER FILE NO.**  
 SCHEDULE - 2  
 PROJECT 01256  
 3/15/10-MDS

**GREENE & BRADFORD, INC.**  
 OF SPRINGFIELD  
 200 WEST HILLMAN DRIVE  
 SPRINGFIELD, ILLINOIS 62767  
 (618) 234-1111 FAX (618) 234-1112  
 WWW.GREENE-AND-BRADFORD.COM