F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
95	*	JASPER	545	28
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

*(5,6)Y,RS-2,6BR-7
CONTRACT NO. 94437

DESIGN		
INT.	DATE	REASON

PLOTS & CHECKS			
INT.	DATE	NO.	REASON

CHECKS		
INT.	DATE	REASON

EARTHWORK SCHEDULE

LOCATION	GRADING AND SHAPING DITCHES	EARTH EXCAVATION (CUT)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT (FILL)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	FOOT	CU YD	CU YD	CU YD	CU YD
ILLINOIS ROUTE 33					
STA. 689+80.27 TO STA. 729+18.46		4,527	3,395	3,430	-35
STA. 715+25.91' RT. TO STA. 715+74.3, 274.8' RT,	190				
STA. 730+07.55 TO STA. 767+18.69		3,488	2,616	3,204	-588
STA. 767+18.69 TO STA. 816+00		3,226	2,420	4,809	-2,390
STA. 753+41.5, 71.5' RT.	1,000				
STA. 810+48.6, 34' RT. TO STA. 810+54.6, 410.5' RT.	377				
STA. 816+00 TO STA. 838+27.25		1,293	970	403	567
STA. 838+62.16 TO STA. 871+80.22		6,291	4,718	3,063	1,655
STA. 871+21.76 TO STA. 881+74.09		2,118	1,589	677	912
STA. 881+74.09 TO STA. 946+27		9,622	7,217	7,721	-505
STA. 946+27 TO STA. 979+98.96		8,196	6,147	3,977	2,170
STA. 979+98.96 TO STA. 1009+22.09		2,476	1,857	1,758	99
STA. 1003+90, 120.7' RT. TO STA. 1005+86, 134' RT.	203				
STA. 1009+22.09 TO STA. 1031+27.73		3,752	2,814	1,737	1,077
STA. 1031+27.73 TO STA. 1057+25.42		1,451	1,088	2,253	-1,165
STA. 1042+66.7, 92.8' RT. TO STA. 1043+15, 281' RT.	290				
STA. 1048+13.1, 96.9' RT. TO STA. 1051+14, 549' RT.	550				
STA. 1057+25.42 TO STA. 1104+93.23		6,003	4,502	4,000	502
STA. 1081+25.00 RT. TO STA. 1082+89.00, RT.	223				
STA. 1104+93.23 TO STA. 1153+37.59		11,694	8,771	5,228	3,543
STA. 1153+37.59 TO STA. 1177+50		3,516	2,637	2,172	465
STA. 1177+50 TO STA. 1189+00		2,033	1,525	2,494	-969
STA. 1189+00 TO STA. 1207+23.26		2,131	1,598	2,905	-1,307
STA. 1206+92.54 TO STA. 1229+20.94		2,412	1,809	1,478	331
STA. 2229+20.94 TO STA. 2231+69.98		502	377	223	154
STA. 2231+69.98 TO STA. 2241+35.11		2,380	1,785	1,994	-209
STA. 2241+35.11 TO STA. 2244+02.86		716	537	364	173
STA. 2244+02.86 TO STA. 2246+85.78		513	385	501	-116
STA. 1246+91.91 TO STA. 1249+00.92		136	102	239	-137
STA. 1249+00.92 TO STA. 1271+05.02		1,177	883	2,962	-2,079
STA. 1271+05.02 TO STA. 1282+42.33		372	279	1,358	-1,079
STA. 1282+42.33 TO STA. 1285+59		62	47	210	-164
T.R. 30 (200E)		186	140	435	-296
T.R. 155 (380E/1300N)		158	119	486	-368
T.R. 56 (400E)		82	62	172	-111
GILA ROAD - FAS 703 (C.H. 21)		31	23	8	15
CIPS ROAD (C.H. 8) (500E)		1,203	902	666	236
T.R. 84 (600E/1800N)		216	162	142	20
T.R. 181 (1150N)		215	161	344	-183
T.R. 92 (700E)		167	125	202	-77
T.R. 102 (775E)		154	116	140	-25
T.R. 120 (850E)		134	101	253	-153
T.R. 201 (1000N)		1,678	1,259	1,594	-336
BOGOTA ROAD (900E)		640	480	467	13
TOTALS	2,833	84,951	63,713	64,069	-356

TEMPORARY CONCRETE BARRIER AND IMPACT ATTTENUATOR SCHEDULE

LOCATION	IMPACT ATTENUATORS TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	IMPACT ATTENUATORS RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER
	EACH	EACH	FOOT	FOOT
ILLINOIS ROUTE 33				
STAGE 1				
STA. 725+75 TO STA. 731+75	2		600	
STAGE 2				
STA. 725+75 TO STA. 731+75		2		600
STAGE 1				
STA. 907+50 TO STA. 909+25	2		175	
STAGE 2				
STA. 907+50 TO STA. 909+25		2		175
STAGE 1				
STA. 1176+90 TO STA. 1179+40	2		250	
STAGE 2				
STA. 1176+90 TO STA. 1179+40		2		250
TOTALS	6	6	1,025	1,025

POROUS GRANULAR EMBANKMENT, SPECIAL SCHEDULE

LOCATION	POROUS GRANULAR EMBANKMENT, SPECIAL
	CU YD
T.R. 30 (200E)	12
BRIDGE (SN 040-0021)	150
T.R. 155 (380E/1300N)	38
T.R. 56 (400E)	12
T.R. 181 (1150N)	21
TOTALS	233

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAP ROUTE 95 (IL RTE. 33)
SECTION (5,6)Y,RS-2,6BR-7
JASPER COUNTY

SCALE: VERT. HORIZ.
DATE: 09/16/02

DRAWN BY: BISHOP
DESIGNED BY: COLBROOK
CHECKED BY: COLBROOK

GREENE & BRADFORD, INC. OF SPRINGFIELD
CONSULTING ENGINEERS
3601 CONSTITUTION DRIVE
SPRINGFIELD, ILLINOIS 62707
PROFESSIONAL DESIGN FIRM NO. 184-000178
PARSONS BRINCKERHOFF QUADE & DOUGLAS, INCORPORATION
(217) 753-3844, (217) 753-9207 (FAX) WWW. GREENEANDBRADFORD.COM

COMPUTER FILE NO.
SCHEDULE - 15

PROJECT 01256
3/16/10-MDS

IDOTPL-50 1"=50' 8/07/00