

DESIGN		
INT.	DATE	REASON

PLOTS & CHECKS			
INT.	DATE	NO.	REASON

CHECKS		
INT.	DATE	REASON

STAGE 2 CONSTRUCTION SCHEDULE
(FOR INFORMATION ONLY)

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
95	.	JASPER	546	111
STA. 710+00.00 TO STA. 740+00.00				
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
*15,61Y,RS-2,6BR-7				
CONTRACT NO. 94437				

SEEDING, CLASS 2

IL RTE. 33

RT. STA. 938+68.58 TO STA. 946+27	=	0.87	ACRES
RT. STA. 946+27 TO STA. 956+66.57	=	0.16	ACRES
CIPS ROAD			
STA. 86+30 TO STA. 89+20	=	0.13	ACRES
STA. 90+70 TO STA. 97+50	=	0.2	ACRES
TOTAL	=	1.36	ACRES

PAVEMENT REMOVAL

CIPS ROAD

STA. 86+30 TO STA. 89+87.95	=	1,246	SQ. YD.
STA. 90+26.92 TO STA. 97+08	=	924	SQ. YD.
TOTAL	=	2,170	SQ. YD.

AGGREGATE SHOULDERS, TYPE B 6"

RT. STA. 938+68.58 TO STA. 946+27	=	343	SQ. YD.
RT. STA. 946+27 TO STA. 956+66.57	=	569	SQ. YD.
TOTAL	=	912	SQ. YD.

HOT-MIX ASPHALT SHOULDERS 6 1/2"

RT. STA. 938+68.58 TO STA. 946+27	=	253	SQ. YD.
RT. STA. 946+27 TO STA. 956+66.57	=	347	SQ. YD.
TOTAL	=	600	SQ. YD.

TEMPORARY PAVEMENT MARKING - LINE 4" *

STA. 938+68 TO STA. 946+27 (WHITE)	=	1,518	FOOT
STA. 946+27 TO STA. 956+56 (WHITE)	=	2,058	FOOT
STA. 938+68 TO STA. 946+27 (YELLOW SKIP-DASH)	=	190	FOOT
STA. 946+27 TO STA. 956+56 (YELLOW SKIP-DASH)	=	260	FOOT
TOTAL	=	4,026	FOOT

WORK ZONE PAVEMENT MARKING REMOVAL **

STA. 938+68 TO STA. 946+27	=	126	SQ. FT.
STA. 946+27 TO STA. 956+56	=	170	SQ. FT.
STA. 938+68 TO STA. 946+27	=	1002	SQ. FT.
STA. 946+27 TO STA. 956+56	=	1,358	SQ. FT.
TOTAL	=	2,656	SQ. FT.

EARTH EXCAVATION

IL RTE. 33

CUT FROM RIGHT SIDE	=	2,995	CU. YD.
TOTAL	=	2,995	CU. YD.

EMBANKMENT

IL RTE. 33


FILL FROM RIGHT SIDE	=	928	CU. YD.
TOTAL	=	928	CU. YD.

- NOTE:
- INSTALLED PRIOR TO STAGE 2 CONSTRUCTION
 - REMOVED UPON COMPLETION OF STAGE 2

ILLINOIS DEPARTMENT OF TRANSPORTATION
STAGE 2 CONSTRUCTION PLAN
C.I.P.S. ROAD CONSTRUCTION

FAP ROUTE 95 (IL RTE. 33)
SECTION (5,6)Y,RS-2,6BR-7
JASPER COUNTY

SCALE: VERT. DRAWN BY: BISHOP
 HORIZ. DESIGNED BY: COLBROOK
DATE: 04/15/03 CHECKED BY: COLBROOK

	GREENE & BRADFORD, INC. OF SPRINGFIELD CONSULTING ENGINEERS INCORPORATED 1984 REGISTERED PROFESSIONAL ENGINEERS STATE OF ILLINOIS 1211 1/2 BANK BLDG. 201 S. 2ND ST. CHICAGO, ILL. 60604 TEL: 312.587.7000 FAX: 312.587.7001 WWW.GRENEBRADFORD.COM	COMPUTER FILE NO. STAGE-16 - 50 PROJECT 01256 3/11/10-MDS
---	---	--

REVISIONS	
NAME	DATE