

**STAGE 3 CONSTRUCTION SCHEDULE**  
(FOR INFORMATION ONLY)

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
95	*	JASPER	546	121
STA. 710+00.00 TO STA. 740+00.00				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
*(5,6)Y,RS-2,6BR-7				
CONTRACT NO. 94437				

**SEEDING, CLASS 2**

IL RTE. 33			
LT. STA. 1175+35 TO STA. 1177+50	=	0.46	ACRES
LT. STA. 1175+50 TO STA. 1189+00	=	1.12	ACRES
LT. STA. 1189+00 TO STA. 1198+13.36	=	0.95	ACRES
P.R. 1000N			
STA. 156+00 TO STA. 159+66	=	0.33	ACRES
STA. 160+65 TO STA. 170+60.48	=	1.84	ACRES
<b>TOTAL</b>	<b>=</b>	<b>5.26</b>	<b>ACRES</b>

**PROCESSING MODIFIED SOIL 12"**

IL RTE. 33			
STA. 1181+43.80 TO STA. 1189+00	=	767	SO. YD.
STA. 1189+00 TO STA. 1198+13.36	=	1,133	SO. YD.
P.R. 1000N			
STA. 156+00 TO STA. 159+87.52	=	1,138	SO. YD.
STA. 160+13.24 TO STA. 170+60.48	=	3,267	SO. YD.
BOGOTA ROAD			
STA. 170+27.67 TO STA. 175+60.48	=	1,718	SO. YD.
<b>TOTAL</b>	<b>=</b>	<b>8,191</b>	<b>SO. YD.</b>

**PAVEMENT REMOVAL**

P.R. 1000N	=	2,179	SO. YD.
<b>TOTAL</b>	<b>=</b>	<b>8,023</b>	<b>SO. YD.</b>

**AGGREGATE SHOULDERS, TYPE B 6"**

IL RTE. 33			
LT. STA. 1181+43.80 TO STA. 1189+00	=	421	SO. YD.
LT. STA. 1189+00 TO STA. 1198+13.36	=	508	SO. YD.
P.R. 1000N			
STA. 156+00 TO STA. 159+87.52	=	261	SO. YD.
STA. 160+13.24 TO STA. 170+60.48	=	699	SO. YD.
BOGOTA ROAD			
STA. 170+27.67 TO STA. 175+61.57	=	356	SO. YD.
<b>TOTAL</b>	<b>=</b>	<b>2,245</b>	<b>SO. YD.</b>

**HOT-MIX ASPHALT BASE COURSE 8"**

P.R. 1000N			
STA. 156+00 TO STA. 159+87.52	=	1,012	SO. YD.
STA. 160+13.24 TO STA. 170+60.48	=	2,824	SO. YD.
BOGOTA ROAD			
STA. 170+27.67 TO STA. 175+61.57	=	1,473	SO. YD.
<b>TOTAL</b>	<b>=</b>	<b>5,309</b>	<b>SO. YD.</b>

**HOT-MIX ASPHALT SHOULDERS 6 1/2"**

LT. STA. 1181+43.80 TO STA. 1189+00	=	252	SO. YD.
LT. STA. 1189+00 TO STA. 1198+13.36	=	305	SO. YD.
<b>TOTAL</b>	<b>=</b>	<b>557</b>	<b>SO. YD.</b>

**TEMPORARY PAVEMENT MARKING - LINE 4" \***

IL RTE. 33			
STA. 1175+35 TO STA. 1177+50 (YELLOW)	=	60	FOOT
STA. 1175+35 TO STA. 1177+50 (WHITE)	=	430	FOOT
STA. 1177+50 TO STA. 1189+00 (YELLOW)	=	290	FOOT
STA. 1177+50 TO STA. 1189+00 (WHITE)	=	2,300	FOOT
STA. 1189+00 TO STA. 1198+14 (YELLOW)	=	230	FOOT
STA. 1189+00 TO STA. 1198+14 (WHITE)	=	1,828	FOOT
P.R. 1000N			
STA. 156+00 TO STA. 159+66 (YELLOW)	=	100	FOOT
STA. 156+00 TO STA. 159+66 (WHITE)	=	695	FOOT
STA. 160+65 TO STA. 170+61 (YELLOW)	=	250	FOOT
STA. 160+65 TO STA. 170+61 (WHITE)	=	1,992	FOOT
BOGOTA ROAD			
STA. 166+50 TO STA. 169+66 (YELLOW)	=	80	FOOT
STA. 166+50 TO STA. 169+66 (WHITE)	=	543	FOOT
STA. 170+65 TO STA. 175+62 (YELLOW)	=	130	FOOT
STA. 170+65 TO STA. 175+62 (WHITE)	=	994	FOOT
<b>TOTAL</b>	<b>=</b>	<b>9,922</b>	<b>FOOT</b>

**TEMPORARY PAVEMENT MARKING LINE 24" \***

P.R. 1000N			
STA. 159+75	=	13	FOOT
STA. 160+25	=	15	FOOT
BOGOTA ROAD			
STA. 170+40	=	12	FOOT
<b>TOTAL</b>	<b>=</b>	<b>40</b>	<b>FOOT</b>

**WORK ZONE PAVEMENT MARKING REMOVAL \*\***

IL RTE. 33			
LT. STA. 1175+35 TO STA. 1177+50	=	162	SO. FT.
STA. 1177+50 TO STA. 1189+00	=	855	SO. FT.
STA. 1189+00 TO STA. 1189+14	=	679	SO. FT.
P.R. 1000N			
STA. 156+00 TO STA. 159+75	=	281	SO. FT.
STA. 160+25 TO STA. 170+60.48	=	769	SO. FT.
STA. 159+75	=	24	SO. FT.
STA. 160+25	=	24	SO. FT.
BOGOTA ROAD			
STA. 170+40 TO STA. 175+62	=	391	SO. FT.
STA. 170+40	=	24	SO. FT.
<b>TOTAL</b>	<b>=</b>	<b>3,128</b>	<b>SO. FT.</b>

**EARTH EXCAVATION**

IL RTE. 33			
CUT FROM LEFT SIDE	=	2,262	CU. YD.
P.R. 1000N			
STA. 156+00 TO STA. 159+66	=	782	CU. YD.
STA. 160+65 TO STA. 170+61	=	1,782	CU. YD.
BOGOTA ROAD			
STA. 170+65 TO STA. 175+62	=	1,048	CU. YD.
<b>TOTAL</b>	<b>=</b>	<b>5,874</b>	<b>CU. YD.</b>

**EMBANKMENT**

IL RTE. 33			
FILL FROM LEFT SIDE	=	2,104	CU. YD.
P.R. 1000N			
STA. 156+00 TO STA. 159+66	=	450	CU. YD.
STA. 160+65 TO STA. 170+61	=	454	CU. YD.
BOGOTA ROAD			
STA. 170+65 TO STA. 175+62	=	89	CU. YD.
<b>TOTAL</b>	<b>=</b>	<b>3,097</b>	<b>CU. YD.</b>

NOTE:

- INSTALLED PRIOR TO STAGE 3 CONSTRUCTION
- REMOVED UPON COMPLETION OF STAGE 3

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**STAGE 3 CONSTRUCTION**  
**SCHEDULE OF QUANTITIES**  
**BOGOTA ROAD CONSTRUCTION**  
FAP ROUTE 95 (IL RTE. 33)  
SECTION (5,6)Y,RS-2,6BR-7  
JASPER COUNTY

SCALE: VERT. \_\_\_\_\_  
HORIZ. \_\_\_\_\_  
DATE: 04/15/03

DRAWN BY: BISHOP  
DESIGNED BY: COLBROOK  
CHECKED BY: COLBROOK

GREENE & BRADFORD, INC.  
OF SPRINGFIELD

COMPUTER FILE NO.  
STG3.CULV - 02

PROJECT 01256  
2/26/10-FAV

REVISIONS	
NAME	DATE