F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
95	*	JASPER	546	127
STA. 710+00.00		TO STA. 740+00.00		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

*(5,6)Y,RS-2,6BR-7
CONTRACT NO. 94437

STAGE 4 CONSTRUCTION SCHEDULE
(FOR INFORMATION ONLY)

SEEDING, CLASS 2

IL RTE. 33

RT. STA. 1175+35 TO STA. 1177+50	=	0.43	ACRES
RT. STA. 1177+50 TO STA. 1189+00	=	1.01	ACRES
RT. STA. 1189+00 TO STA. 1198+13.36	=	0.87	ACRES

BOGOTA ROAD

STA. 166+50 TO STA. 169+17	=	0.19	ACRES
STA. 170+70 TO STA. 175+73.57	=	0.85	ACRES
TOTAL	=	3.35	ACRES

PROCESSING MODIFIED SOIL 12"

BOGOTA ROAD

STA. 166+50 TO STA. 169+87.95	=	1,767	SQ. YD.
TOTAL	=	1,767	SQ. YD.

PAVEMENT REMOVAL

BOGOTA ROAD	=	2,945	SQ. YD.
TOTAL	=	2,945	SQ. YD.

AGGREGATE SHOULDERS, TYPE B 6"

IL RTE. 33

RT. STA. 1177+50 TO STA. 1189+00	=	639	SQ. YD.
RT. STA. 1189+00 TO STA. 1198+13.36	=	370	SQ. YD.

BOGOTA ROAD

STA. 166+50 TO STA. 169+87.95	=	223	SQ. YD.
TOTAL	=	1,232	SQ. YD.

HOT-MIX ASPHALT BASE COURSE 8"

BOGOTA ROAD	=	1,389	SQ. YD.
TOTAL	=	1,389	SQ. YD.

HOT-MIX ASPHALT SHOULDERS 6½"

IL RTE. 33

RT. STA. 1181+43.80 TO STA. 1189+00	=	169	SQ. YD.
RT. STA. 1189+00 TO STA. 1198+13.36	=	203	SQ. YD.
TOTAL	=	372	SQ. YD.

COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24

BOGOTA ROAD	=	22	FOOT
TOTAL	=	22	FOOT

TEMPORARY PAVEMENT MARKING - LINE 4" *

BOGOTA ROAD

STA. 166+50 TO STA. 169+88 (YELLOW)	=	80	FOOT
STA. 166+50 TO STA. 169+88 (WHITE)	=	543	FOOT
TOTAL	=	623	FOOT

TEMPORARY PAVEMENT MARKING LINE 24" *

BOGOTA ROAD

STA. 169+75	=	39	FOOT
TOTAL	=	39	FOOT

WORK ZONE PAVEMENT MARKING REMOVAL **

BOGOTA ROAD

STA. 169+75	=	78	SQ. FT.
STA. 166+50 TO STA. 169+75	=	206	SQ. FT.
TOTAL	=	284	SQ. FT.

CONCRETE MEDIAN SURFACE, 4 INCH

BOGOTA ROAD	=	37	SQ. FT.
TOTAL	=	37	SQ. FT.

COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06

BOGOTA ROAD	=	6	FOOT
TOTAL	=	6	FOOT

EARTH EXCAVATION

IL RTE. 33

CUT FROM RIGHT SIDE	=	2,262	CU. YD.

BOGOTA ROAD

STA. 166+50 TO STA. 169+75	=	530	CU. YD.
TOTAL	=	2,792	CU. YD.

EMBANKMENT

IL RTE. 33

FILL FROM RIGHT SIDE	=	2,104	CU. YD.

BOGOTA ROAD

STA. 166+50 TO STA. 169+75	=	213	CU. YD.
TOTAL	=	2,317	CU. YD.

NOTE:
- * INSTALLED PRIOR TO STAGE 4 CONSTRUCTION
- ** REMOVED UPON COMPLETION OF STAGE 4

DESIGN		
INT.	DATE	REASON

PLOTS & CHECKS			
INT.	DATE	NO.	REASON

CHECKS		
INT.	DATE	REASON

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

STAGE 4 CONSTRUCTION SCHEDULE OF QUANTITIES
BOGOTA ROAD CONSTRUCTION

FAP ROUTE 95 (IL RTE. 33)
SECTION (5,6)Y,RS-2,6BR-7
JASPER COUNTY

SCALE: VERT. HORIZ.
DATE: 04/15/03

DRAWN BY: BISHOP
DESIGNED BY: COLBROOK
CHECKED BY: COLBROOK

GREENE & BRADFORD, INC.
OF SPRINGFIELD
CONSULTING ENGINEERS
1011 SOUTH 2ND STREET
SPRINGFIELD, ILLINOIS 62707
PROFESSIONAL DESIGN FIRM NO. 184-000170
PROFESSIONAL & STRUCTURAL ENGINEERING CORPORATION
(217) 793-3844, (217) 793-3227 (FAX) e-mail: - cooley@greenebradfordsfld.com

COMPUTER FILE NO. STG4_CULV - 02
PROJECT 01256
2/26/10-FAV

IDOTPL-30 1"=30' 8/07/00

STAGE CONSTRUCTION - T.R. 210 (900E)/BOGOTA ROAD - JASPER COUNTY