

STAGE 2 CONSTRUCTION SCHEDULE
(FOR INFORMATION ONLY)

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
95	*	JASPER	546	135
STA. 710+00.00		TO STA. 740+00.00		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
*(5,6)Y,RS-2,6BR-7				
CONTRACT NO. 94437				

SEEDING, CLASS 1

LT. STA. 2231+69.98 TO STA. 2238+94	=	0.74	ACRES
LT. STA. 2238+94 TO STA. 2241+35.11	=	0.46	ACRES
LT. STA. 2241+35.11 TO STA. 2244+02.86	=	0.25	ACRES
LT. STA. 2244+02.86 TO STA. 2246+85.78	=	0.18	ACRES
TOTAL	=	1.63	ACRES

PAVEMENT REMOVAL

APPLE SHED ROAD	=	234	SQ. YD.
TOTAL	=	234	SQ. YD.

AGGREGATE SHOULDERS, TYPE B 6"

LT. STA. 2231+69.98 TO STA. 2238+94	=	293	SQ. YD.
TOTAL	=	293	SQ. YD.

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24

LT STA. 2244+02.86 TO STA. 2246+85.78	=	294	FOOT
TOTAL	=	294	FOOT

HOT-MIX ASPHALT CONCRETE BINDER COURSE, IL - 19.0, N70

STA. 2231+69.98 TO STA. 2241+35.11 (ALONG OLD ALIGNMENT)	=	561	TON
TOTAL	=	561	TON

TEMPORARY PAVEMENT MARKING - LINE 4" *

STA. 2231+69.98 TO STA. 2241+35.11 (WHITE)	=	1,449	FOOT
STA. 2231+69.98 TO STA. 2241+35.11 (YELLOW)	=	250	FOOT
STA. 2241+35.11 TO STA. 2244+02.86 (YELLOW)	=	70	FOOT
STA. 2244+02.86 TO STA. 2246+85.78 (YELLOW)	=	80	FOOT
TOTAL	=	1,849	FOOT

WORK ZONE PAVEMENT MARKING REMOVAL **

STA. 2231+69.98 TO STA. 2241+35.11	=	561	SQ. FT.
STA. 2241+35.11 TO STA. 2244+02.86	=	24	SQ. FT.
STA. 2244+02.86 TO STA. 2246+85.78	=	27	SQ. FT.
TOTAL	=	612	SQ. FT.

EARTH EXCAVATION

CUT FROM LEFT SIDE	=	1,544	CU. YD.
TOTAL	=	1,544	CU. YD.

EMBANKMENT

FILL FROM LEFT SIDE	=	1,687	CU. YD.
TOTAL	=	1,687	CU. YD.

HOT-MIX ASPHALT SHOULDERS 8"

STA. 223+69.98 TO STA. 2238+94	=	176	SQ. YD.
TOTAL	=	176	SQ. YD.

NOTE:

- INSTALLED PRIOR TO STAGE 2 CONSTRUCTION
- REMOVED UPON COMPLETION OF STAGE 2

ILLINOIS DEPARTMENT OF TRANSPORTATION
STAGE 2 CONSTRUCTION SCHEDULE OF QUANTITIES
RELOCATION IN NEWTON
FAP ROUTE 95 (IL RTE. 33)
SECTION (5,6)Y,RS-2,6BR-7
JASPER COUNTY

SCALE: VERT. DRAWN BY: BISHOP
 HORIZ. DESIGNED BY: COLBROOK
 DATE: 04/15/03 CHECKED BY: COLBROOK

COMPUTER FILE NO.
STAGE-23 - 20
PROJECT 01256
2/26/10-FAV

REVISIONS	
NAME	DATE



DESIGN		
INT.	DATE	REASON

PLOTS & CHECKS		
INT.	DATE	REASON

CHECKS		
INT.	DATE	REASON