

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
95	•	JASPER	546	215
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
*15,61Y,RS-2,6BR-7 CONTRACT NO. 94437				

URBAN ENTRANCE SCHEDULE													
TYPE	SIDE/ STATION	L1 FOOT	L2 FOOT	W1 FOOT	W2 FOOT	AGGREGATE BASE COURSE, TYPE B TON	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 FOOT	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70 TON	PORTLAND CEMENT CONCRETE PAVEMENT 8" SQ YD	PAVEMENT FABRIC SQ YD	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT		DRIVEWAY PAVEMENT REMOVAL SQ YD
											6" SQ YD	8" SQ YD	
IL RTE 33													
C.E.	2241+90, LT.	30	51	95	35		177					311	
C.E.	2245+56, LT.	30	0	58	24		72					109	
C.E.	1251+78, LT.	30	0	84	24		72					109	131
C.E.	1253+06, LT.	30	0	84	24		72					109	121
C.E.	1253+84, RT.	30	30	84	24							251	279
C.E.	1253+90, LT.												121
C.E.	1254+84, LT.	30	0	84	24		72					109	
P.E.	1255+98, LT.	30	0		13						49		43
C.E.	1256+58, RT.	30	30	84	24							248	298
C.E.	1257+44, LT.	30	0	84	24		72					109	63
C.E.	1258+37, RT.	30	0	84	24							149	
C.E.	1258+67, LT.	30	0	84	24		72					109	43
C.E.	1260+02, LT.	30	0	84	24		72					109	23
MB TURNOUT	1260+06, RT.												31
C.E.	1261+19, LT.	30	0	84	24		72					109	26
C.E.	1262+22, LT.	30	0	84	24		72					109	
MB TURNOUT	1262+64, RT.												31
P.E.	1262+80, LT.	30	0		12						42		
C.E.	1263+57, RT.	30	0	95	35		72					145	138
P.E.	1264+04, LT.	30	0		12						42		
P.E.	1266+84, RT.	30	20		16						79		
P.E.	1267+22, LT.	30	0		20						68		
P.E.	1268+88, RT.	30	0		12						44		
C.E.	1273+92, LT.	30	0	84	24		52					74	23
C.E.	1274+89, LT.	30	0	84	24		52					74	23
C.E.	1279+46, RT.	30	0	84	24		68					104	167
C.E.	1282+47, RT.	30	0	84	24		68					104	98
P.E.	1284+52, LT.	21	0		12						8		
MUSEUM DR. STREET	2241+35.11, RT.	30	-	-	28				157	157			
APPLE SHED RD. STREET	2244+02.86, LT.	30	50	-	24	67		15	132	132			
GREGORY DR. STREET	1249+00.92, LT.	30	50	-	20	60		14	123	123			
STREET	1249+03.18, RT.								400	400			
P.E.	220+62, RT.	11	35	50	12						60		69
HUTTON RD. STREET	271+03.28, LT.	30	50	-	20	61		14	123	123			
STREET	271+05.02, RT.	30	50	-	21	63		15	123	123			
P.E.	230+64, LT.	6	0	2	12						23		
HOMESTEAD RD. STREET	1282+42, LT.	30	50	-	20	61		14	126	126			
TOTALS						312	1,137	72	1,184	1,184	415	2,503	1,666

* BITUMINOUS MATERIALS AND AGGREGATE (PRIME COAT) FOR ENTRANCES AND PUBLIC ROAD APPROACHES SHALL BE CONSIDERED INCIDENTAL TO THE COST OF HOT-MIX ASPHALT SURFACE COURSE, MIX C N70

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
URBAN ENTRANCE SCHEDULE
 FAP ROUTE 95 (IL RTE. 33)
 SECTION (5,6)Y,RS-2,6BR-7
 JASPER COUNTY

SCALE: VERT. DRAWN BY: BISHOP
 HORIZ. DESIGNED BY: COLBROOK
 DATE: 09/18/02 CHECKED BY: COLBROOK

GREENE & BRADFORD, INC.
 OF SPRINGFIELD
 CONSULTING ENGINEERS
 1001 EAST WASHINGTON STREET
 SPRINGFIELD, ILLINOIS 62761
 (618) 233-8844 (618) 233-8877 FAX (618) 233-8844 www.greenegb.com

COMPUTER FILE NO.
 ENTRANCE - 50
 PROJECT 01256
 2/26/10-FAV