STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAP 95	6BR-7	JASPER	546	246
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT-	

SHEET NO. 6
18 SHEETS

Contract No. 94437

STAGE CONSTRUCTION LINE

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflections
Bk. W. Abut.	72929.40	3.500	583.890	583.890
CL Brg. W. Abut.	72930.86	3.500	583.883	583.883
A	72940.86	3.500	583.833	583.912
B	72950.86	3.500	583.784	583.930
C	72960.86	3.500	583.734	583.929
D	72970.86	3.500	583.684	583.903
E	72980.86	3.500	583.635	583.850
F	72990.86	3.500	583.585	583.771
G	73000.86	3.500	583.536	583.667
H	73010.86	3.500	583.486	583.545
CL Brg. E. Abut.	73018.19	3.500	583.450	583.450
Bk. E. Abut	73019.65	3.500	583.443	583.443

BEAM 5

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflections
Bk. W. Abut.	72930.99	6.250	583.839	583.839
CL Brg. W. Abut.	72932.45	6.250	583.832	583.832
A	72942.45	6.250	583.782	583.861
B	72952.45	6.250	583.733	583.879
C	72962.45	6.250	583.683	583.878
D	72972.45	6.250	583.634	583.852
E	72982.45	6.250	583.584	583.799
F	72992.45	6.250	583.535	583.720
G	73002.45	6.250	583.485	583.616
H	73012.45	6.250	583.435	583.494
CL Brg. E. Abut.	73019.78	6.250	583.399	583.399
Bk. E. Abut	73021.24	6.250	583.392	583.392

BEAM 6

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflections
Bk. W. Abut.	72934.60	12.500	583.721	583.721
CL Brg. W. Abut.	72936.06	12.500	583.714	583.714
A	72946.06	12.500	583.664	583.743
B	72956.06	12.500	583.615	583.761
C	72966.06	12.500	583.565	583.760
D	72976.06	12.500	583.515	583.734
E	72986.06	12.500	583.466	583.681
F	72996.06	12.500	583.416	583.602
G	73006.06	12.500	583.367	583.498
H	73016.06	12.500	583.317	583.376
CL Brg. E. Abut.	73023.39	12.500	583.281	583.281
Bk. E. Abut	73024.85	12.500	583.274	583.274

BEAM 7

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflections
Bk. W. Abut.	72938.21	18.750	583.573	583.573
CL Brg. W. Abut.	72939.66	18.750	583.566	583.566
A	72949.66	18.750	583.516	583.595
B	72959.66	18.750	583.466	583.613
C	72969.66	18.750	583.417	583.612
D	72979.66	18.750	583.367	583.586
E	72989.66	18.750	583.318	583.533
F	72999.66	18.750	583.268	583.453
G	73009.66	18.750	583.219	583.350
H	73019.66	18.750	583.169	583.228
CL Brg. E. Abut.	73027.00	18.750	583.133	583.133
Bk. E. Abut	73028.46	18.750	583.125	583.125

E-S 4-30-97

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

TOP OF SLAB ELEVATIONS (2 OF 2)

IL RTE 33 OVER WEST FORK OF BIG MUDDY CREEK
FAP RTE 95 - SECTION 6BR-7
JASPER COUNTY
STATION 729+72.50
SN 040-0021

SCALE: VERT. HORIZ.
DATE: 8/25/04

DRAWN BY: LANDREY
DESIGNED BY: SANFORD
CHECKED BY: WATKINS

GREENE & BRADFORD, INC.
OF SPRINGFIELD
CONSULTING ENGINEERS
1500 CONSTITUTION DRIVE
SPRINGFIELD, ILLINOIS 62704
PROFESSIONAL DESIGN FIRM 184-001073
PROFESSIONAL & STRUCTURAL ENGINEERING CORPORATION
(217) 793-3844, (217) 753-5231 (FAX) FAX. - GBSPRINGFIELD@CTCNET.COM

COMPUTER FILE NO. 01256TOS1
PROJECT 01256
2/26/10-FAV

BRIDGE PLANS - F.A.P. ROUTE 95 (IL RTE. 33) JASPER COUNTY

FILE NAME = J:\01256\DRAWINGS\SN040-0021\01256TOS1.dgn
PLOT SCALE = 1.0000 in / DMU = V8I_TDS700.PS:LOCAL.pltcfg
PLOT DATE = 3/17/2010
PLOT TIME = 5:15:30 PM
OPERATOR = ffranky