

### SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITIES
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	62
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	114
20100500	TREE REMOVAL, ACRES	ACRE	0.50
S 20200100	EARTH EXCAVATION	CU YD	2,960
S 20800150	TRENCH BACKFILL	CU YD	47
S 25000200	SEEDING, CLASS 2	ACRE	0.75
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	68
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	68
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	68
25100115	MULCH, METHOD 2	ACRE	0.75
25100630	EROSION CONTROL BLANKET	SQ YD	504
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	150
28000305	TEMPORARY DITCH CHECKS	FOOT	104
28000400	PERIMETER EROSION BARRIER	FOOT	739
28000500	INLET AND PIPE PROTECTION	EACH	11
S 28100105	STONE RIPRAP, CLASS A3	SQ YD	66
28200200	FILTER FABRIC	SQ YD	66
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	2,066
35102400	AGGREGATE BASE COURSE, TYPE B 12"	SQ YD	283
40200500	AGGREGATE SURFACE COURSE, TYPE A 6"	SQ YD	37
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	20
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,297
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1,453
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2,178
S 42000400	PORTLAND CEMENT CONCRETE PAVEMENT 9"	SQ YD	1,511
42001200	PAVEMENT FABRIC	SQ YD	1,511

CODE NO.	ITEM	UNIT	TOTAL QUANTITIES
S 42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	149
S 42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	11,367
S 44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	6,534
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	190
44000300	CURB REMOVAL	FOOT	1,512
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	674
44000600	SIDEWALK REMOVAL	SQ FT	8,890
S 44200948	CLASS B PATCHES, TYPE I, 9 INCH	SQ YD	14
S 44200956	CLASS B PATCHES, TYPE II, 9 INCH	SQ YD	82
S 44200962	CLASS B PATCHES, TYPE III, 9 INCH	SQ YD	16
S 44200964	CLASS B PATCHES, TYPE IV, 9 INCH	SQ YD	196
S 44200978	CLASS B PATCHES, TYPE I, 11 INCH	SQ YD	2
S 44200982	CLASS B PATCHES, TYPE II, 11 INCH	SQ YD	6
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	2,327
S 50104400	CONCRETE HEADWALL REMOVAL	EACH	1
50105220	PIPE CULVERT REMOVAL	FOOT	42
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	37
542D1093	PIPE CULVERTS, CLASS D, TYPE 2 48"	FOOT	51
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1
S 54215550	METAL END SECTIONS 15"	EACH	2
S 54215583	METAL END SECTIONS 48"	EACH	1
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	149
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	7
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1
S 60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	4

CODE NO.	ITEM	UNIT	TOTAL QUANTITIES
S 60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	5
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1
60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	3
60260400	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	3
S 60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	19
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	4
60500060	REMOVING INLETS	EACH	6
S 60600605	CONCRETE CURB, TYPE B	FOOT	122
S 60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1,987
67100100	MOBILIZATION	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4,546
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	694
72000100	SIGN PANEL - TYPE 1	SQ FT	40
72900200	METAL POST - TYPE B	FOOT	97
• 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	390
• 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	23,180
• 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	279
• 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	246
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	298
78300100	PAVEMENT MARKING REMOVAL	SQ FT	204
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	223
• S 88600100	DETECTOR LOOP, TYPE I	FOOT	1,010
S X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1
S Z0064560	SEGMENTAL BLOCK RETAINING WALL	SQ FT	891

• SPECIALTY ITEM  
S SEE PROJECT SPECIFIC SPECIAL PROVISION