

WILLIAMSON COUNTY				
F. A. P. 331 (IL 13)				
80% FEDERAL / 20% STATE				
ROADWAY	BNSF RAILROAD BRIDGE	MARATHON DR BRIDGE	MSE WALLS	LIGHTING & TRAFFIC SIGNALS
STA. 1729+56.07 TO STA. 1767+07.23	100-0093 100-0094	100-0095 100-0096	100-W001 100-W002 100-W003	

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE				
				0003	0008	0008	0040 0008	0021
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	138	138				
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	211	211				
20100500	TREE REMOVAL, ACRES	ACRE	0.6	0.6				
20200100	EARTH EXCAVATION	CU YD	28,600	28,600				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	306	306				
20400800	FURNISHED EXCAVATION	CU YD	121,690	121,690				
20800150	TRENCH BACKFILL	CU YD	1,282.9	1,282.9				
X 25000115	SEEDING, CLASS 1B	ACRE	9.75	9.75				
X 25000350	SEEDING, CLASS 7	ACRE	9.75	9.75				
X 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1,560	1,560				
X 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1,170	1,170				
X 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1,170	1,170				
X 25000700	AGRICULTURAL GROUND LIMESTONE	TON	19.5	19.5				
X 25100115	MULCH, METHOD 2	ACRE	19.50	19.50				

X SPECIALTY ITEM

FILE NAME =	USER NAME = Matt Overbay	DESIGNED -	REVISED -
I:\dot\0906683\draw\cadd\sheet\099885	sh-900801.dgn	DRAWN -	REVISED -
	PLOT SCALE = 50.0000' / 1" = 1'	CHECKED -	REVISED -
	PLOT DATE = 12/14/2011	DATE = 12/9/11	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
ILLINOIS ROUTE 13**

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	(IX-1) VB-1, B-1, N-4, R-3	WILLIAMSON	367	4
SCALE: N/A			CONTRACT NO. 98859	
SHEET NO. OF SHEETS		STA. N/A TO STA. N/A		
ILLINOIS FED. AID PROJECT				