

WILLIAMSON COUNTY				
F. A. P. 331 (IL 13)				
80% FEDERAL / 20% STATE				
ROADWAY	BNSF RAILROAD BRIDGE	MARATHON DR BRIDGE	MSE WALLS	LIGHTING & TRAFFIC SIGNALS
STA. 1729+56.07 TO STA. 1767+07.23	100-0093 100-0094	100-0095 100-0096	100-W001 100-W002 100-W003	

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE				
				0003	0008	0008	0008	0021
X 25100630	EROSION CONTROL BLANKET	SQ YD	25,621	25,621				
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	246	246				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	975	975				
28000305	TEMPORARY DITCH CHECKS	FOOT	456	456				
28000400	PERIMETER EROSION BARRIER	FOOT	1,058	1,058				
28000500	INLET AND PIPE PROTECTION	EACH	87	87				
28001000	AGGREGATE (EROSION CONTROL)	TON	3.9	3.9				
28100105	STONE RIPRAP, CLASS A3	SQ YD	1,120	1,120				
28100107	STONE RIPRAP, CLASS A4	SQ YD	95	95				
28200200	FILTER FABRIC	SQ YD	95	95				
30200950	PROCESSING MODIFIED SOIL 18"	SQ YD	567	567				
30201500	LIME	TON	18.4	18.4				
31100300	SUBBASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	8,514	8,514				
31100700	SUBBASE GRANULAR MATERIAL, TYPE A 8"	SQ YD	42,691	42,691				

X SPECIALTY ITEM

FILE NAME #	USER NAME = Matt Overbey	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES ILLINOIS ROUTE 13			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1:\dot\0906603\draw\codd.sheets\099085	shht-500001.dgn	DRAWN -	REVISED -					331	(1X-1) VB-1, B-1, N-4, R-3	WILLIAMSON	367	5
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -		SCALE: N/A			SHEET NO. OF SHEETS		STA. N/A	TO STA. N/A	
	PLOT DATE = 12/14/2011	DATE - 12/9/11	REVISED -		CONTRACT NO. 98859 ILLINOIS FED. AID PROJECT							