

WILLIAMSON COUNTY				
F. A. P. 331 (IL 13)				
80% FEDERAL / 20% STATE				
ROADWAY	BNSF RAILROAD BRIDGE	MARATHON DR BRIDGE	MSE WALLS	LIGHTING & TRAFFIC SIGNALS
STA. 1729+56.07 TO STA. 1767+07.23	100-0093 100-0094	100-0095 100-0096	100-W001 100-W002 100-W003	

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE				
				0003	0008	0008	0008	0021
31100900	SUBBASE GRANULAR MATERIAL, TYPE A 10"	SQ YD	6,190	6,190				
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	12,235	12,235				
31200100	STABILIZED SUBBASE 4"	SQ YD	41,113	41,113				
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	227.9	227.9				
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	6,691.6	6,691.6				
40600300	AGGREGATE (PRIME COAT)	TON	16.4	16.4				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	371	371				
40600990	TEMPORARY RAMP	SQ YD	1,430	1,430				
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	56.8	56.8				
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N105	TON	745.3	745.3				
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	655.6	655.6				
40603575	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N105	TON	252.5	252.5				
40701881	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10"	SQ YD	10,702	10,702				
42000411	PORTLAND CEMENT CONCRETE PAVEMENT 9 1/2" (JOINTED)	SQ YD	36,114	36,114				

FILE NAME =	USER NAME = Matt Overbey	DESIGNED -	REVISED -
3:\dot\9906603\draw\cadd\sheet\099859	sh1-S0201.dgn	DRAWN -	REVISED -
	PLOT SCALE = 50.0000' / 1"	CHECKED -	REVISED -
	PLOT DATE = 12/14/2011	DATE = 12/9/11	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES  
ILLINOIS ROUTE 13**

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	(IX-1) VB-1, B-1, N-4, R-3	WILLIAMSON	367	6
SCALE: N/A			CONTRACT NO. 98859	
SHEET NO. OF SHEETS		ILLINOIS FED. AID PROJECT		