

WILLIAMSON COUNTY				
F. A. P. 331 (IL 13)				
80% FEDERAL / 20% STATE				
ROADWAY	BNSF RAILROAD BRIDGE	MARATHON DR BRIDGE	MSE WALLS	LIGHTING & TRAFFIC SIGNALS
STA. 1729+56.07 TO STA. 1767+07.23	100-0093 100-0094	100-0095 100-0096	100-W001 100-W002 100-W003	

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE				
				0003	0008	0008	0008	0021
42001200	PAVEMENT FABRIC	SQ YD	2,173	2,173				
42001300	PROTECTIVE COAT	SQ YD	43,895	43,895				
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	4,322	4,322				
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	262	262				
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	9,037	9,037				
42400800	DETECTABLE WARNINGS	SQ FT	22	22				
44000100	PAVEMENT REMOVAL	SQ YD	36,841	36,841				
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	5,495	5,495				
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	990	990				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	3,015	3,015				
44003100	MEDIAN REMOVAL	SQ FT	1,106	1,106				
44004000	PAVED DITCH REMOVAL	FOOT	497	497				
44004250	PAVED SHOULDER REMOVAL	SQ YD	11,309	11,309				
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	37	37				

FILE NAME =	USER NAME = Matt Overbey	DESIGNED -	REVISED -
I:\dot\0906683\draw\cadd\sheet\099885	sheet-500001.dgn	DRAWN -	REVISED -
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 12/14/2011	DATE = 12/9/11	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
ILLINOIS ROUTE 13**

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	(IX-1) VB-1, B-1, N-4, R-3	WILLIAMSON	367	7
SCALE: N/A			SHEET NO. OF SHEETS STA. N/A TO STA. N/A	
ILLINOIS FED. AID PROJECT CONTRACT NO. 98859				