

WILLIAMSON COUNTY				
F. A. P. 331 ( IL 13)				
80% FEDERAL / 20% STATE				
ROADWAY	BNSF RAILROAD BRIDGE	MARATHON DR BRIDGE	MSE WALLS	LIGHTING & TRAFFIC SIGNALS
STA. 1729+56.07 TO STA. 1767+07.23	100-0093 100-0094	100-0095 100-0096	100-W001 100-W002 100-W003	

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE				
				0003	0008	0008	0008	0021
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	124	124				
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	104	104				
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1				
70300100	SHORT TERM PAVEMENT MARKING	FOOT	3,082	3,082				
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	1,966	1,966				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	92,905	92,905				
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	4,033	4,033				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	268	268				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1,738	1,738				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1,225	1,225				
X 70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	1,454	1,454				
X 70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	28,444	28,444				
X 70300530	PAVEMENT MARKING TAPE, TYPE III 5"	FOOT	4,033	4,033				
X 70300540	PAVEMENT MARKING TAPE, TYPE III 6"	FOOT	268	268				
X								

X SPECIALTY ITEM

FILE NAME =	USER NAME = Matt Overbay	DESIGNED -	REVISED -
Is:\dot\0986603\draw\cadd\sheet\099865	sh-t-500001.dgn	DRAWN -	REVISED -
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 12/14/2011	DATE = 12/9/11	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

<b>SUMMARY OF QUANTITIES</b>			
<b>ILLINOIS ROUTE 13</b>			
SCALE: N/A	SHEET NO. OF	SHEETS	STA. N/A TO STA. N/A

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	(1X-1) VB-1, B-1, N-4, R-3	WILLIAMSON	367	15
CONTRACT NO. 98859				
ILLINOIS FED. AID PROJECT				