

WILLIAMSON COUNTY				
F. A. P. 331 (IL 13)				
80% FEDERAL / 20% STATE				
ROADWAY	BNSF RAILROAD BRIDGE	MARATHON DR BRIDGE	MSE WALLS	LIGHTING & TRAFFIC SIGNALS
STA. 1729+56.07 TO STA. 1767+07.23	100-0093 100-0094	100-0095 100-0096	100-W001 100-W002 100-W003	

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE				
				0003	0008	0008	0008	0021
84200804	REMOVAL OF POLE FOUNDATION	EACH	10					10
85700300	FULL-ACTUATED CONTROLLER AND TYPE V CABINET	EACH	2					2
X 86200300	UNINTERRUPTIBLE POWER SUPPLY, EXTENDED	EACH	2					2
X 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	5,814					5,814
X 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	3,822					3,822
X 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	6,269					6,269
X 87301815	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 3C	FOOT	152					152
X 87502680	TRAFFIC SIGNAL POST, ALUMINUM 14 FT.	EACH	2					2
X 87502700	TRAFFIC SIGNAL POST, ALUMINUM 16 FT.	EACH	4					4
X 87702920	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	2					2
X 87702940	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 42 FT.	EACH	2					2
X 87702985	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 52 FT.	EACH	1					1
X 87702990	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 54 FT.	EACH	1					1
X 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	18					18
X								

X SPECIALTY ITEM

FILE NAME =	USER NAME = Matt Overbey	DESIGNED -	REVISED -
I:\vict\0426603\draw\cadd\sheet\099885	sh-t-000001.dgn	DRAWN -	REVISED -
	PLOT SCALE = 50.0000 / IN.	CHECKED -	REVISED -
	PLOT DATE = 12/14/2011	DATE = 12/9/11	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES ILLINOIS ROUTE 13			
SCALE: N/A	SHEET NO. OF	SHEETS	STA. N/A TO STA. N/A

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	(IX-1) VB-1, B-1, N-4, R-3	WILLIAMSON	367	20
CONTRACT NO. 98859			ILLINOIS FED. AID PROJECT	