

WILLIAMSON COUNTY				
F. A. P. 331 (IL 13)				
80% FEDERAL / 20% STATE				
ROADWAY	BNSF RAILROAD BRIDGE	MARATHON DR BRIDGE	MSE WALLS	LIGHTING & TRAFFIC SIGNALS
STA. 1729+56.07 TO STA. 1767+07.23	100-0093 100-0094	100-0095 100-0096	100-W001 100-W002 100-W003	

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE				
				0003	0008	0008	0040 0008	0021
Z0022800	FENCE REMOVAL	FOOT	662	662				
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 2	EACH	1	1				
X Z0030255	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	9	9				
X Z0030322	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	6	6				
Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	1	1				
X Z0033062	RADIO TRANSCEIVER	EACH	2					2
Z0034210	MECHANICALLY STABILIZED EARTH RETAINING WALL	SQ FT	73,493				73,493	
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	312		312			
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1				
X Z0049100	RAISED PAVEMENT MARKER REFLECTOR REPLACEMENT	EACH	48	48				
Z0056100	SAND DRAINAGE BLANKET	CU YD	9,145.4	9,145.4				
Z0056608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	125	125				
Z0056610	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FOOT	202	202				
Z0056616	STORM SEWER (WATER MAIN REQUIREMENTS) 24 INCH	FOOT	33	33				

X SPECIALTY ITEM

FILE NAME =	USER NAME = Matt Overbey	DESIGNED -	REVISED -
I:\dot\0906603\draw\cadd\sheet\099885	ph-t-500001.dgn	DRAWN -	REVISED -
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 12/14/2011	DATE = 12/9/11	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES ILLINOIS ROUTE 13			
SCALE: N/A	SHEET NO. OF	SHEETS	STA. N/A TO STA. N/A

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	(IX-1) VB-1, B-1, N-4, R-3	WILLIAMSON	367	24
CONTRACT NO. 98859			ILLINOIS FED. AID PROJECT	