

STORM SEWERS (CONTINUED)

STATION / LOCATION	STORM SEWERS, CLASS A, TYPE 1						STORM SEWERS, CLASS A, TYPE 2				STORM SEWERS, CLASS A, TYPE 6 24"	STORM SEWERS, CLASS A, TYPE 2 EQ. ROUND-SIZE 30"	STORM SEWER (WATER MAIN REQUIREMENTS)				PRECAST REINFORCED CONCRETE FLARED END SECTIONS						CONCRETE COLLAR (CU YD)	TRENCH BACKFILL (CU YD)		
	12"	15"	18"	24"	30"	36"	12"	15"	18"	24"			12"	15"	24"	54"	12"	15"	18"	24"	30"	36"			54"	
	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)			(FOOT)	(FOOT)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)			(EACH)	(EACH)
SKYLINE DRIVE (SOUTH)																										
1+62.10																										
2+39.61																										
2+70.87						63																				7.4
2+83.06																										10.1
2+83.06																										3.3
3+18.90																										3.1
3+47.63																										6.3
3+63.70																										13.9
3+63.70																										5.7
SKYLINE DRIVE (NORTH)																										
11+35.02																										
12+60.61																										
13+27.61																										
15+66.24																										
16+02.36																										
16+02.39	21.99'																									
MARATHON DRIVE																										
8+18.58	27.77'																									
8+21.76																										
TOTALS																										
		1,078	33	38	63	180	13	543	70	6	115	73	38	125	202	33	57	4	1	2	2	2	1	1	4.1	572.4

*SEE PIPE CULVERTS, AND INLETS AND MANHOLES SCHEDULES FOR ADDITIONAL QUANTITIES

PIPE CULVERTS AND PIPE DRAINS SCHEDULE

STATION / LOCATION	PIPE CULVERTS, CLASS A, TYPE 2		PIPE CULVERTS, CLASS A, TYPE 1 EQ. ROUND-SIZE 24"	PRECAST REINFORCED CONCRETE FLARED END SECTIONS			METAL END SECTIONS 12"	PIPE DRAINS, 12"	CONCRETE THRUST BLOCKS (EACH)	TRENCH BACKFILL (CU YD)		
	36"	54"		36"	54"	EL EQ RS 24"						
	(FOOT)	(FOOT)		(EACH)	(EACH)	(EACH)						
IL 13												
1734+80.00	110.78'	LT										
1734+94.46		LT		21								
1742+05.00		LT						92	1			
1742+05.00	156.30'	LT						1				
1753+70.33		LT						77	1			
1753+70.33	143.91'	LT						1				
FRONTAGE ROAD												
474+97.36	42.17'	LT				1						
475+05.20		LT	15									
475+19.44			43									
475+37.19		RT	30							8.1		
475+45.52	55.54'	RT				1				2.6		
SKYLINE DRIVE												
6+51.54	29.68'	RT						1				
6+55.77										12.8		
6+60.00	60.03'	LT						1				
TOTALS			88	21	78	2	1	2	2	169	2	23.5

*SEE STORM SEWERS, AND INLETS AND MANHOLES SCHEDULES FOR ADDITIONAL QUANTITIES

FILE NAME =	USER NAME = Matt Overbay	DESIGNED - MJO	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3:\dot\0906603\draw\cadd\sheet\099885	sht-Schedules.dgn	DRAWN - MJO	REVISED -						331	(1X-1) VB-1, B-1, N-4, R-3	WILLIAMSON	367	42
	PLOT SCALE = 50.0000' / IN.	CHECKED - BMB	REVISED -						CONTRACT NO. 98859				
	PLOT DATE = 12/14/2011	DATE - 12/9/11	REVISED -						ILLINOIS FED. AID PROJECT				