

EROSION CONTROL BLANKET

STATION / LOCATION				EROSION CONTROL BLANKET
STATION	TO	STATION		(SQ YD)
IL 13				
1731+63	-	1735+35	LT	1,836
1736+03	-	1741+97	LT	4,910
1736+13	-	1737+57	RT	603
1737+00	-	1744+66	STAGE 1 SIDESLOPE	3,405
1748+00	-	1752+15	STAGE 1 SIDESLOPE	3,136
1753+01	-	1760+00	STAGE 1 SIDESLOPE	3,107
1753+93	-	1760+50	LT	4,028
1759+18	-	1760+00	RT	292
1763+50	-	1767+06	LT	1,467
FRONTAGE ROAD				
461+13	-	461+59	RT	56
471+74	-	474+70	LT	839
471+74	-	475+14	RT	781
474+58	-	476+65	LT	785
475+14	-	476+65	RT	376
TOTALS				25,621

TREE REMOVAL

STATION / LOCATION			TREE REMOVAL (6-15 UNITS)	TREE REMOVAL (OVER 15 UNITS)	TREE REMOVAL, ACRES
			(UNITS)	(UNITS)	ACRE
IL 13					
1737+15.22	132.51'	LT		18	
1747+89.08	75.60'	RT	6		
1748+17.33	76.59'	RT	6		
1748+26.58	75.52'	RT	6		
1748+83.22	74.99'	RT	6		
1750+65.19	63.90'	RT	6		
1751+41.23	42.65'	RT		18	
1753+25.15	69.88'	RT		27	
1753+27.68	110.37'	RT		24	
1753+53.05	64.45'	RT	12		
1754+35.42	47.01'	RT		18	
1754+70.03	44.00'	RT		18	
1755+06.65	42.49'	RT	15		
1755+38.71	57.95'	RT		24	
1758+61.85	63.03'	RT		24	
1758+63.47	73.37'	RT		40	
1759+73.55	58.97'	RT	15		
1760+01.12	84.76'	RT	12		
1760+40.66	89.45'	RT	12		
FRONTAGE ROAD					
472+85.62					0.6
MARATHON DRIVE					
12+05.29	11.22'	RT	6		
12+25.01	9.21'	RT	6		
14+22.44	0.19'	LT	6		
14+45.26	0.44'	RT	6		
14+65.53	0.24'	RT	6		
14+85.64	0.59'	RT	6		
15+06.70	0.97'	RT	6		
TOTALS			138	211	0.6

PERIMETER EROSION BARRIER

STATION / LOCATION				PERIMETER EROSION BARRIER
STATION	TO	STATION		(FOOT)
IL 13				
1730+84	-	1731+33	RT	54
FRONTAGE ROAD				
461+48	-	462+22	RT	87
471+73	-	472+15	LT	63
474+00	-	475+14	RT	115
475+23	-	475+47	RT	24
SKYLINE DRIVE (SOUTH)				
6+34	-	6+50	RT	24
6+55	-	8+14	RT	160
6+62	-	9+45	LT	310
MARATHON DRIVE				
10+81	-	13+14	LT	221
TOTALS				1,058