

TEMPORARY PAVEMENT MARKING

STATION / LOCATION			TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS (SQ FT)	TEMPORARY PAVEMENT MARKING - LINE 4"			TEMPORARY PAVEMENT MARKING - LINE 12"	TEMPORARY PAVEMENT MARKING - LINE 24"	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL	RAISED PAVEMENT MARKER REFLECTOR REPLACEMENT	WORK ZONE PAVEMENT MARKING REMOVAL (SQ FT)	PAVEMENT MARKING REMOVAL (SQ FT)
				WHITE (FOOT)	YELLOW (FOOT)	BLACK (FOOT)	YELLOW (FOOT)	WHITE (FOOT)	(EACH)	(EACH)	(EACH)	(EACH)	(SQ FT)	(SQ FT)
STAGE 1B														
IL 13														
710+00.00	-	1725+00.00			882	882					12	12	588	
1725+00.00	-	1738+00.00	48	2,811	1,910	1,064		70	24	48	14	14	969	1,004
1738+00.00	-	1751+00.00		3,260	2,608				34	68				1,074
1751+00.00	-	1764+00.00	32	2,893	2,360			96	30	64				1,018
1764+00.00	-	1775+00.00		1,434	1,590	1,051			14	28	8	8	1,013	950
SKYLINE DRIVE			48	442	420			71						426
MARATHON DRIVE			32	290	260			26						100
SINCLAIR DRIVE			48	291	35			45					247	413
STAGE 1B SUBTOTALS			208	11,421	10,065	2,997	0	308	102	208	34	34	2,817	4,985
STAGE 1C														
SKYLINE DRIVE														
STAGE 1C SUBTOTALS			0	193	338	0	0	0	0	0	0	0	177	0
STAGE 1D														
SKYLINE DRIVE														
STAGE 1D SUBTOTALS			32	913	646	0	0	24	0	0	0	0	600	0
STAGE 1E														
SKYLINE DRIVE														
STAGE 1E SUBTOTALS			32	537	702	0	0	0	0	0	0	0	445	0
STAGE 1F														
SKYLINE DRIVE														
STAGE 1F SUBTOTALS			0	1,316	716	0	0	0	0	0	0	0	678	0
STAGE 2A														
IL 13														
1725+00.00	-	1738+00.00	48	3,118	1,956	612	34	93	26	26	4	4	2,164	
1738+00.00	-	1751+00.00		3,254	2,597		16		34	34			1,967	
1751+00.00	-	1764+00.00	32	3,548	2,385			55	32	32			2,120	
1764+00.00	-	1775+00.00		1,593	1,119	158			12	12	10	10	957	
SKYLINE DRIVE			48	1,393	1,134		160	59					1,169	58
SINCLAIR DRIVE			32	226	162			25						
STAGE 2A SUBTOTALS			160	13,132	9,353	770	210	232	104	104	14	14	8,377	58
STAGE 2B														
SKYLINE DRIVE														
STAGE 2B SUBTOTALS			0	912	1,147	0	68	0	0	0	0	0	754	635
STAGE 2C														
SKYLINE DRIVE														
STAGE 2C SUBTOTALS			0	724	1,620	0	115	0	0	0	0	0	897	0
STAGE 2D														
SKYLINE DRIVE														
STAGE 2D SUBTOTALS			0	1,138	1,231	0	68	0	0	0	0	0	858	0
STAGE 2E														
SKYLINE DRIVE														
STAGE 2E SUBTOTALS			0	381	597	0	34	10	0	0	0	0	380	0
STAGE 2F														
SKYLINE DRIVE														
STAGE 2F SUBTOTALS			80	1,634	1,978	0	48	36	0	0	0	0	1,404	0
TOTALS			512	32,301	28,393	3,767	543	610	206	312	48	48	17,387	5,678

• REFLECTOR REPLACEMENTS SHALL OCCUR IN STAGE 3 OR WHEN TRAFFIC IS RETURNED TO THE PROPOSED CONFIGURATION
 TEMPORARY RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE REMOVED WHEN CONFLICTING WITH SUBSEQUENT TRAFFIC CONFIGURATIONS OR WHEN NO LONGER NEEDED
 TEMPORARY PAVEMENT MARKINGS SHALL BE REMOVED WHEN CONFLICTING WITH SUBSEQUENT TRAFFIC CONFIGURATIONS