MEDIAN NOSE RADIUS POINTS
- (E) STA. 1762+10.91, 14.00′ LT.
- (F) STA. 1762+11.64, 10.14′ LT.
- (G) STA. 1762+04.67, 7.72′ LT.
- (H) STA. 1762+10.91, 12.00′ LT.

PR RADIUS 90′

PR RADIUS POINTS
- (A) STA. 1761+75.17, 69.13′ LT.
- (B) STA. 1761+29.64, 56.00′ LT.

PR RADIUS 50′

PR RADIUS POINTS
- (C) STA. 1763+47.13, 68.00′ LT.
- (D) STA. 1763+27.51, 72.22′ LT.

N

20′ 0 20′ 40′
SCALE: 1″ = 20′

EXISTING PAVEMENT JOINTS (TYP.)

STA. 1761+95.31, 84.78′ LT.
MATCH EXISTING CURB AND GUTTER

REMOVE AND REPLACE EXISTING CURB AND GUTTER
SEE STAGING PLANS FOR DETAILS

STA. 1761+84.63, 75.10′ LT.
MATCH EXISTING CURB AND GUTTER

MATCH EXISTING CURB AND GUTTER
STA. 1763+18.02, 76.52′ LT.

31° 00′ 04.46″ R=90′
16.21′ CH. (TYP.)
22° 34′ 22.81″ R=50′
20.43′ CH.

ROLL FROM 2.7% SE
TO EX. 2.0% SE
(STA. 1765+84.90)

1762+52.60, 35.91′ LT. ℄ ILLINOIS ROUTE 13 =
10+00.00 EXISTING ℄ SINCLAIR DRIVE

FILE NAME = L:\IDOT\09006603\Draw\CADD_Sheets\D998859-sht-intersec003.dgn	USER NAME = OpenH&B Springfield	DESIGNED - BMB	REVISED -
		DRAWN - GLD	REVISED -
	PLOT SCALE = 20.0000 ′ / IN.	CHECKED - SPH	REVISED -
	PLOT DATE = 12/14/2011	DATE - 12/9/11	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

INTERSECTION DETAIL
ILLINOIS ROUTE 13 AND SINCLAIR DR.

SCALE: 1″ = 20′ | SHEET NO. OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	(IX-1) VB-1, B-1, N-4, R-3	WILLIAMSON	367	129
		CONTRACT NO. 98859		
	ILLINOIS FED. AID PROJECT			