



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 22, 2018

SUBJECT: FAP Route 313 (US 34/IL 110)
Project NHPP-QBQZ(237)
Section 94(16,16-1,17)RS, 48(17,18)RS
Knox and Warren Counties
Contract No. 68339
Item No. 31, March 9, 2018 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Table of Contents to the Special Provisions
2. Revised pages 7-9 of the Special Provisions
3. Deleted sheets 110-113 of the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

Jack A. Elston, P.E.
Acting Bureau Chief
Bureau of Design and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger P.E.'.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Kensil Garnett, Region 3, District 4; Tim Kell; D. Carl Puzey; Estimates

JW/ck

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
CONSTRUCTION STATION LAYOUT	2
LOCATION OF UNDERGROUND STATE MAINTAINED FACILITIES	2
EMBANKMENT	3
SEEDING, MINOR AREAS	3
MOWING	4
STONE DUMPED RIPRAP 3	4
PROOF ROLLING	4
SUBGRADE TREATMENT	5
SUBBASE GRANULAR MATERIAL	5
HOT-MIX ASPHALT SURFACE COURSE SURFACE TESTS	5
PAYMENT FOR USE OF MATERIAL TRANSFER DEVICE	6
REFLECTIVE CRACK CONTROL TREATMENT	6
GUARDRAIL AGGREGATE EROSION CONTROL	7
RECOVERABLE DELINEATORS	10
EQUIPMENT VAULT FOR NUCLEAR TESTING EQUIPMENT	11
TRAFFIC CONTROL PLAN	11
TRAFFIC CONTROL AND PROTECTION (SPECIAL)	14
GROOVING FOR RECESSED PAVEMENT MARKING	15
AGGREGATE QUALITY	17
PCC QC/QA ELECTRONIC REPORTS SUBMITTAL	17
PCC AUTOMATIC BATCHING EQUIPMENT	18
CLASS A PATCHES, TYPE IV, 11 INCH	18
CLASS D PATCHES TYPE III, 9" (SPECIAL)	19
CLASS SI CONCRETE FOR PIPE UNDERDRAIN OUTLET	19
GRADING AND SHAPING DITCHES	19
HMA SURFACE REMOVAL, VARIABLE DEPTH	20
INLET TO BE ADJUSTED WITH NEW FRAME AND GRATE (SPECIAL)	20
JOINT FILLING WITH MICROSURFACING MATERIAL	21
PAVED SHOULDER REMOVAL	23
REVTMENT MAT REMOVAL	23
SHOULDER REMOVAL AND REPLACEMENT, SPECIAL	23

CONSTRUCTION SEQUENCE FOR MAINLINE PAVEMENT AND SHOULDERS.....24
 WORKING RESTRICTIONS.....25
 LOCATION OF UNDERGROUND STATE MAINTAINED FACILITIES25
 CONTRACT GUARANTEE.....26
 LIGHT POLE, GALVANIZED STEEL, 45 FT. M.H., TENON MOUNT-TWIN.....26
 LUMINAIRE, LED, HORIZONTAL MOUNT, OF THE WATTAGE SPECIFIED27
 GUARDRAIL TO BE SALVAGED34
 PIPE UNDERDRAIN 4" (SPECIAL)34
 MATERIAL TRANSFER DEVICE (BDE)35
 RECLAIMED ASPHALT PAVEMENT AND RECLAIMED ASPHALT SHINGLES (MODIFIED FOR
 I-FIT PROJECTS ONLY)36
 HOT-MIX ASPHALT – MIXTURE DESIGN VERIFICATION AND PRODUCTION (MODIFIED
 FOR I-FIT PROJECTS ONLY) (CBM)46
 JACK AND REMOVE EXISTING BEARINGS49
 CLEANING AND PAINTING CONTACT SURFACE AREAS OF EXISTING STEEL
 STRUCTURES50
 CLEANING AND PAINTING EXISTING STEEL STRUCTURES56
 CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES81
 DECK SLAB REPAIR107
 BRIDGE DECK MICROSILICA CONCRETE OVERLAY.....113
 STRUCTURAL REPAIR OF CONCRETE125
 BRIDGE DECK CONSTRUCTION135
 ADJUSTING FRAMES AND GRATES (BDE)137
 BUTT JOINTS (BDE).....139
 CLASS A AND B PATCHING (BDE)140
 COMPENSABLE DELAY COSTS (BDE).....140
 DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE).....144
 EQUIPMENT PARKING AND STORAGE (BDE)156
 HOT MIX ASPHALT - PAY FOR PERFORMANCE USING PERCENT WITHIN LIMITS -JOBSITE
 SAMPLING (BDE).....157
 HOT-MIX ASPHALT – TACK COAT (BDE)162
 LIGHTS ON BARRICADES (BDE)163
 PAYMENTS TO SUBCONTRACTORS (BDE)164
 PORTLAND CEMENT CONCRETE (BDE)164

PROGRESS PAYMENTS (BDE)	165
SPEED DISPLAY TRAILER (BDE).....	166
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)	167
SURFACE TESTING OF HOT-MIX ASPHALT OVERLAYS (BDE).....	168
TRAINING SPECIAL PROVISIONS (BDE)	169
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION	171
WARM MIX ASPHALT (BDE)	174
WEEKLY DBE TRUCKING REPORTS (BDE).....	176
WORKING DAYS (BDE).....	176
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE).....	177
FUEL COST ADJUSTMENT (BDE).....	178
STEEL COST ADJUSTMENT (BDE).....	181

Add after the first paragraph of Article 443.06:

"If the asphalt cement binder bleeds through the fabric under traffic, then a fine aggregate blotter shall be applied as directed by the Engineer and paid for in accordance with Article 109.04 of the Standard Specifications.

After reflective crack control placement and prior to the HMA overlay placement, the Contractor shall furnish, erect and maintain SLIPPERY WHEN WET signs at such locations when required during wet weather. The cost of this work shall be included in the unit prices bid and no additional compensation will be allowed."

GUARDRAIL AGGREGATE EROSION CONTROL

Effective February 1, 1993

Revised January 1, 2007

This work shall consist of furnishing, placing, and shaping crushed aggregate placed around and behind guardrail posts in accordance with plan details.

Method of Measurement: The aggregate for constructing the Guardrail Aggregate Erosion Control will be measured in Tons (Metric Tons).

The Geotextile Fabric will not be measured for payment.

Basis of Payment: Guardrail Aggregate Erosion Control will be paid for at the contract unit price per Ton (Metric Ton) for GUARDRAIL AGGREGATE EROSION CONTROL measured as specified herein. The Geotextile Fabric will not be measured for payment, but shall be included in the cost per Ton (Metric Ton) for GUARDRAIL AGGREGATE EROSION CONTROL.

Revised 2-22-18

Page intentionally left blank.

Page intentionally left blank.