

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	91 Y - T	COOK	12	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		URBAN Y007					
20200100	EARTH EXCAVATION	CU YD	120	120					
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	75	75					
20800150	TRENCH BACKFILL	CU YD	45	45					
28000500	INLET AND PIPE PROTECTION	EACH	2	2					
28000510	INLET FILTERS	EACH	2	2					
42001300	PROTECTIVE COAT	SQ YD	70	70					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5"	SQ FT	50	50					
44000600	SIDEWALK REMOVAL	SQ FT	50	50					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	20	20					
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	40	40					
55039700	STORM SEWERS TO BE CLEANED	FOOT	25	25					
67100100	MOBILIZATION	L SUM	1	1					
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	25.7	25.7					
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	4	4					
XX004210	DUCTILE IRON PIPE STORM SEWERS, 12"	FOOT	50	50					
XX146400	STORM SEWER REMOVAL	FOOT	35	35					
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	1	1					
XX006262	STEEL CASING PIPE AUGERED AND JACKED 24"	FOOT	55	55					

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT							

12/13/2005 8:58:03 AM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

Rev.