

← RURAL → ← URBAN →

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
309	16R-2	WHITESIDE	547	6
STA.	TO STA.			
FED. ROAD DIST. NO. 2 ILLINOIS		FED. AID PROJECT		

SUMMARY OF QUANTITIES				WHITESIDE COUNTY							
				80% FEDERAL / 20% STATE							
				CONSTRUCTION TYPE CODE							
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY	ROADWAY	CULVERT	CULVERT	RETAINING WALL	RETAINING WALL	MINOR	
				I000-2A	I000-2A	X028-2A	X028-2A	Y007	Y007	STRUCTURES (1)	
				URBAN	RURAL	SN 098-2021	SN 098-2025	SN 098-7001	SN 098-7002	Y007	
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	42,183	31,446	10,737						
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	120	48	72						
35101400	AGGREGATE BASE COURSE, TYPE B	TON	2,496	2,090	406						
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	544	476	68						
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	48.4	33.5	14.9						
40500300	BITUMINOUS MIXTURE COMPLETE	TON	5,390	3,231	2,159						
40600300	AGGREGATE (PRIME COAT)	TON	45	33	12						
40600895	CONSTRUCTING TEST STRIP	EACH	2	2							
40600995	TEMPORARY RAMP, SPECIAL	SQ YD	1,539	725	814						
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	770	727	43						
42001300	PROTECTIVE COAT	SQ YD	7,288	7,288							
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	1,957	1,957							
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	221	221							
44000030	BITUMINOUS SURFACE REMOVAL (VARIBLE DEPTH)	SQ YD	1,832	1,832							
44000100	PAVEMENT REMOVAL	SQ YD	15,106	13,232	1,874						
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1,086	1,086							
44000300	CURB REMOVAL	FOOT	24	24							
44000400	GUTTER REMOVAL	FOOT	991	991							
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2,992	2,992							
44000600	SIDEWALK REMOVAL	SQ FT	26	26							
44004250	PAVED SHOULDER REMOVAL	SQ YD	2,897	1,690	1,207						
44004300	PAVEMENT BREAKING	SQ YD	3,376	428	2,948						
48100100	AGGREGATE SHOULDERS, TYPE A	TON	2,189	1,209	980						
48202400	BITUMINOUS SHOULDERS SUPERPAVE 6"	SQ YD	4,644	3,484	1,160						
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1			1					

(1) CULVERT-CATTLE PASS
* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FAP ROUTE 309 (US 30)
SECTION 16R-2, EAST CONTRACT
FROM 0.2 MILE EAST OF JACKSON ST.
TO FRENCH CREEK
WHITESIDE COUNTY
SCALE: N.T.S. DRAWN BY CAM
DATE 09/01/05 CHECKED BY RDY