

← RURAL → ← URBAN →

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
309	16R-2	WHITESIDE	547	9
STA.	TO STA.			
FED. ROAD DIST. NO. 2		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES				WHITESIDE COUNTY								
				80% FEDERAL / 20% STATE								
CODE NO. PAY ITEM UNIT TOTAL QUANTITY				CONSTRUCTION TYPE CODE								
				ROADWAY I000-2A URBAN	ROADWAY I000-2A RURAL	CULVERT X028-2A SN 098-2021	CULVERT X028-2A SN 098-2025	RETAINING WALL Y007 SN 098-7001	RETAINING WALL Y007 SN 098-7002	MINOR STRUCTURES (1) Y007		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	4,111.0	4111.0								
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	4		4							
61140000	STORM SEWERS, SPECIAL 8"	FOOT	200		200							
61140100	STORM SEWERS, SPECIAL 10"	FOOT	200		200							
61140200	STORM SEWERS, SPECIAL 12"	FOOT	200		200							
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	12.5	12.5								
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2								
63200310	GUARDRAIL REMOVAL	FOOT	1,310	303	1,007							
63500105	DELINEATORS	EACH	6	2	4							
66400560	CHAIN LINK FENCE, 6' (SPECIAL)	FOOT	457	457								
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	21		21							
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	3		3							
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	20	12	8							
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	20	12	8							
67100100	MOBILIZATION	L SUM	1	1								
70100200	TRAFFIC CONTROL AND PROTECTION, STANDARD 701331	EACH	4	2	2							
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1								
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1								
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1								
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1								
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	170	170								
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	468	406	62							
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	47,314	34,045	13,269							
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	778	778								
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2,705	1,471	1,234							

(1) CULVERT-CATTLE PASS  
\* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
FAP ROUTE 309 (US 30)  
SECTION 16R-2, EAST CONTRACT  
FROM 0.2 MILE EAST OF JACKSON ST.  
TO FRENCH CREEK  
WHITESIDE COUNTY

SCALE: N.T.S. DRAWN BY CAM  
DATE 09/01/05 CHECKED BY RDY