

← RURAL → ← URBAN →

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
309	16R-2	WHITESIDE	547	11
STA.	TO STA.			
FED. ROAD DIST. NO. 2		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES				WHITESIDE COUNTY							
				80% FEDERAL / 20% STATE							
				CONSTRUCTION TYPE CODE							
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY	ROADWAY	CULVERT	CULVERT	RETAINING WALL	RETAINING WALL	MINOR	
				I000-2A	I000-2A	X028-2A	X028-2A	Y007	Y007	STRUCTURES (1)	
				URBAN	RURAL	SN 098-2021	SN 098-2025	SN 098-7001	SN 098-7002	Y007	
Δ Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	2	2							
* Z0049800	RELOCATE EXISTING SURVEY MARKERS	EACH	1		1						
Z0065767	SLOTTED DRAIN 15" WITH 1 3/4" SLOT	FOOT	172	172							
* A2001714	TREE, ACER SACCHARUM (SUGAR MAPLE), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	9	9							
* A2006514	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	9	9							
* A2007814	TREE, TILIA AMERICANA (AMERICAN LINDEN/ BASSWOOD), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	9	9							
* B2002716	TREE, MALUS ADIRONDACK (ADIRONDACK CRAB APPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	9	9							
* B2004814	TREE, MALUS SARGENTII (SARGENT CRABAPPLE) 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	10	10							
* B2005214	TREE, MALUS SUTYZAM (SUGAR TYME CRAB APPLE), 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	10	10							
XX001135	PAVEMENT PATCHING SPECIAL	SQ YD	220	220							
XX003305	SALVAGE AGGREGATE MATERIAL	SQ YD	10,344	9,040	1,304						
XX146400	STORM SEWER REMOVAL	FOOT	408	408							
XZ127900	RETAINING WALL REMOVAL	FOOT	19	19							
* X0322033	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	172	172							
X0322923	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	1,119	1,119							
X0322946	REMOVE CONCRETE BOX CULVERT END SECTION	EACH	2							2	
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	560				560				
X0324056	REMOVAL OF EXISTING WOOD BOLLARDS	EACH	18	18							
* X0324455	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	6,035					3,941	2,094		
X0919000	TEMPORARY PAVEMENT REMOVAL	SQ YD	18,874	11,163	7,711						
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	518	388	130						
X4066740	LEVELING BINDER (HAND METHOD), SUPERPAVE N70	TON	10.0	10.0							
X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	437	437							
* X7200400	WORK ZONE PUBLIC INFORMATION SIGNS	EACH	4	2	2						
X9079139	POLYMERIZED BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 13"	SQ YD	24,423	18,227	6,196						

(1) CULVERT-CATTLE PASS
* SPECIALTY ITEM

Δ SFTY - 3N

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FAP ROUTE 309 (US 30)
SECTION 16R-2, EAST CONTRACT
FROM 0.2 MILE EAST OF JACKSON ST.
TO FRENCH CREEK
WHITESIDE COUNTY
SCALE: N.T.S. DRAWN BY CAM
DATE 09/01/05 CHECKED BY RDY