

F.A.P. SECTION COUNTY TOTAL SHEETS SHEET NO.	309 16R-2 WHITESIDE 547 26
STA. TO STA.	
FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT	

PAY CODE		25000350	25100115	28000250
TEMPORARY EROSION CONTROL SEEDING SCHEDULE				
LOCATION		SEEDING CLASS 7	MULCH METHOD 2	TEMPORARY EROSION CONTROL SEEDING POUND
US RTE 30 - URBAN				
STA. 1115+15.00	TO STA. 1120+00.00	LT		24.32
STA. 1114+50.00	TO STA. 1120+00.00	RT		58.16
STA. 1120+00.00	TO STA. 1126+00.00	LT		122.06
STA. 1120+00.00	TO STA. 1126+00.00	RT		151.14
STA. 1126+00.00	TO STA. 1132+00.00	LT		173.75
STA. 1126+00.00	TO STA. 1132+00.00	RT		149.47
STA. 1132+00.00	TO STA. 1138+00.00	LT	0.81	682.85
STA. 1132+00.00	TO STA. 1138+00.00	RT	0.18	186.09
STA. 1138+00.00	TO STA. 1144+00.00	LT	0.78	590.14
STA. 1138+00.00	TO STA. 1144+00.00	RT	0.27	219.07
STA. 1144+00.00	TO STA. 1150+00.00	LT	0.23	236.12
STA. 1144+00.00	TO STA. 1150+00.00	RT	0.43	363.62
STA. 1150+00.00	TO STA. 1156+00.00	LT		114.20
STA. 1150+00.00	TO STA. 1156+00.00	RT	0.32	241.69
STA. 1156+00.00	TO STA. 1157+00.00	LT		14.93
STA. 1156+00.00	TO STA. 1157+00.00	RT	0.04	42.50
SCENIC STREET				
STA. 15+50.00	TO STA. 16+00.00	LT		3.01
STA. 15+50.00	TO STA. 16+30.00	RT		11.16
SAWYER ROAD				
STA. 7+00.00	TO STA. 8+97.50	LT		34.20
STA. 7+00.00	TO STA. 8+97.50	RT		62.88
SYCAMORE STREET				
STA. 5+50.00	TO STA. 6+00.00	LT		5.72
STA. 5+50.00	TO STA. 6+00.00	RT		3.61
BISHOP ROAD				
STA. 210+94.15	TO STA. 212+31.00	LT		15.08
STA. 210+94.15	TO STA. 213+82.25	RT		49.52
SUBTOTAL - URBAN		3.25	3.25	3,556
US RTE 30 - RURAL				
STA. 1157+00.00	TO STA. 1162+00.00	LT		227.43
STA. 1157+00.00	TO STA. 1162+00.00	RT	0.31	306.94
STA. 1162+00.00	TO STA. 1168+00.00	LT		179.89
STA. 1162+00.00	TO STA. 1168+00.00	RT	0.15	208.70
STA. 1168+00.00	TO STA. 1174+30.00	LT		224.37
STA. 1168+00.00	TO STA. 1174+30.00	RT	0.33	313.82
STA. 1174+30.00	TO STA. 1178+30.00	LT		38.53
STA. 1174+30.00	TO STA. 1178+30.00	RT	0.06	78.41
SUBTOTAL - RURAL		1.00	1.00	1,579
TOTAL		4.25	4.25	5,135

PAY CODE		25100630		
EROSION CONTROL BLANKET SCHEDULE				
LOCATION		WIDTH	LENGTH	EROSION CONTROL BLANKET SQ YD
US RTE 30 - URBAN				
STA. 1133+50.00	TO STA. 1134+50.00	LT	16.0	100.0
STA. 1140+25.00	TO STA. 1144+00.00	LT	26.0	375.0
STA. 1144+00.00	TO STA. 1144+50.00	LT	26.0	50.0
STA. 1140+50.00	TO STA. 1144+00.00	RT	16.0	350.0
STA. 1144+00.00	TO STA. 1146+75.00	RT	16.0	275.0
STA. 1145+00.00	TO STA. 1146+75.00	LT	16.0	175.0
STA. 1146+75.00	TO STA. 1147+75.00	LT	8.0	100.0
STA. 1146+75.00	TO STA. 1150+00.00	RT	16.0	325.0
STA. 1150+00.00	TO STA. 1156+00.00	RT	16.0	600.0
STA. 1153+25.00	TO STA. 1156+00.00	LT	16.0	275.0
STA. 1156+00.00	TO STA. 1156+75.00	RT	16.0	75.0
SUBTOTAL - URBAN				5,184
US RTE 30 - RURAL				
STA. 1170+25.00	TO STA. 1172+00.00	LT	26.0	175.0
SUBTOTAL - RURAL				506
TOTAL				5,690

PAY CODE		28000300	
TEMPORARY DITCH CHECK SCHEDULE			
LOCATION		LEFT	RIGHT
US RTE 30 - URBAN			
STA. 1121+50.00		1	
STA. 1122+25.00		1	
STA. 1123+50.00			1
STA. 1124+00.00			1
STA. 1131+00.00			1
STA. 1132+00.00		1	
STA. 1133+50.00		1	
STA. 1134+25.00		1	1
STA. 1135+00.00		1	
STA. 1135+50.00		1	
STA. 1136+00.00		1	
STA. 1136+50.00		1	
STA. 1137+00.00		1	
STA. 1137+50.00		1	
STA. 1138+00.00		1	
STA. 1138+50.00		1	
STA. 1139+00.00		1	
STA. 1139+25.00			1
STA. 1139+50.00		1	1
STA. 1139+75.00		1	
STA. 1140+00.00		1	
STA. 1140+25.00			1
STA. 1140+50.00		1	1
STA. 1140+75.00		1	1
STA. 1141+00.00		1	1
STA. 1141+25.00		1	1
STA. 1141+50.00		1	1
STA. 1141+75.00		1	1
STA. 1142+00.00		1	1
STA. 1142+25.00		1	1
STA. 1142+50.00		1	1
STA. 1142+75.00		1	1
STA. 1143+00.00		1	1
STA. 1143+25.00		1	1
STA. 1143+50.00		1	1
STA. 1143+75.00		1	1
STA. 1144+00.00		1	1
STA. 1144+25.00		1	
STA. 1144+50.00			1
STA. 1145+00.00			1
STA. 1145+25.00		1	
STA. 1145+50.00		1	1
STA. 1145+75.00		1	
STA. 1146+00.00			1
STA. 1146+25.00		1	1
STA. 1147+25.00		1	1
STA. 1147+50.00		1	1
STA. 1147+75.00		1	1
STA. 1148+00.00		1	1
STA. 1148+25.00		1	1
STA. 1148+50.00		1	1
STA. 1148+75.00		1	1
STA. 1149+00.00		1	1
STA. 1149+25.00		1	1
STA. 1150+75.00		1	1
STA. 1151+25.00		1	1
STA. 1151+75.00		1	1
STA. 1152+25.00		1	1
STA. 1152+75.00		1	1
STA. 1153+25.00		1	1
STA. 1153+75.00		1	1
STA. 1154+25.00		1	1
STA. 1154+75.00		1	1
STA. 1155+25.00		1	1
STA. 1155+75.00		1	1
STA. 1156+25.00		1	1
STA. 1156+75.00		1	1
STA. 1156+95.00		1	1
SUBTOTAL - URBAN		36	52
TOTAL - URBAN		88	

LOCATION	EARTH EXCAVATION (E) CU YD	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE CU YD	EMBANKMENT (F) CU YD	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) CU YD
ROUTE 30 - STAGE 1	3459.63	2594.73	2029.05	665.67
ROUTE 30 - STAGE 2	20470.31	15352.73	494.43	14858.30
SCENIC STREET - STAGE 2	309.55	232.16	0.87	231.30
SYCAMORE STREET - STAGE 2	131.87	98.90	0.00	98.90
ROUTE 30 - STAGE 3	4354.50	3265.88	796.68	2469.20
SAWYER ROAD - STAGE 3	470.33	352.75	601.52	-248.77
DAIRY QUEEN - STAGE 3	674.78	506.09	0.00	506.09
ROUTE 30 - STAGE 4	3456.58	2592.44	1110.58	1481.85
BISHOP ROAD - STAGE 4	337.83	253.37	484.31	-230.93
ROUTE 30 - STAGE 5	1968.75	1476.57	1017.08	459.48
ROUTE 30 - STAGE 6	1217.21	912.91	1566.97	-854.07
SUBTOTAL - URBAN		36,855	8,105	19,540
RURAL				
ROUTE 30 - STAGE 1	1777.69	1333.27	835.74	497.53
ROUTE 30 - STAGE 4	2482.91	1862.18	7894.44	-6032.26
ROUTE 30 - STAGE 5	863.55	647.66	4462.23	-3814.57
ROUTE 30 - STAGE 6	1139.37	854.53	240.52	614.01
SUBTOTAL - RURAL		6,265	13,435	(8,735)
TOTAL		43,120	21,540	10,805

PAY CODE		28000300	
TEMPORARY DITCH CHECK SCHEDULE			
LOCATION		LEFT	RIGHT
US RTE 30 - RURAL			
STA. 1157+15.00			1
STA. 1157+35.00			1
STA. 1157+55.00		1	1
STA. 1157+75.00		1	1
STA. 1157+95.00		1	1
STA. 1159+00.00		1	1
STA. 1160+00.00		1	1
STA. 1161+00.00		1	1
STA. 1162+00.00		1	1
STA. 1163+00.00		1	1
STA. 1164+00.00		1	1
STA. 1165+00.00		1	1
STA. 1166+00.00		1	1
STA. 1167+00.00		1	1
STA. 1167+50.00		1	1
STA. 1168+00.00		1	1
STA. 1168+50.00		1	1
STA. 1169+00.00		1	1
STA. 1169+50.00		1	1
STA. 1170+25.00		1	1
STA. 1170+45.00		1	1
STA. 1170+65.00		1	1
STA. 1170+85.00		1	1
STA. 1171+05.00		1	1
STA. 1171+25.00		1	1
STA. 1171+45.00		1	1
STA. 1171+75.00		1	1
STA. 1172+25.00		1	1
STA. 1173+50.00		1	1
SUBTOTAL - RURAL		24	19
TOTAL - RURAL		43	131

PAY CODE		20200100	
EARTH SUMMARY SCHEDULE			
LOCATION		EARTH EXCAVATION CU YD	
US RTE 30 - URBAN			
US RTE 30 - URBAN			34,927.00
SCENIC STREET			309.55
SAWYER ROAD			470.33
SYCAMORE STREET			131.87
DAIRY QUEEN PARKING LOT			674.78
BISHOP ROAD			337.83
SUBTOTAL - URBAN			36,855
US RTE 30 - RURAL			
US RTE 30 - RURAL			6,263.52
SUBTOTAL - RURAL			6,265
TOTAL			43,120

PAY CODE		28000500		
INLET AND PIPE PROTECTION SCHEDULE				
LOCATION		INLET AND PIPE PROTECTION EACH		
US RTE 30 - URBAN				
STA. 1115+15.00	TO STA. 1120+00.00	LT		1
STA. 1114+50.00	TO STA. 1120+00.00	RT		1
STA. 1120+00.00	TO STA. 1126+00.00	LT		4
STA. 1120+00.00	TO STA. 1126+00.00	RT		4
STA. 1126+00.00	TO STA. 1132+00.00	LT		10
STA. 1126+00.00	TO STA. 1132+00.00	RT		5
STA. 1132+00.00	TO STA. 1138+00.00	RT		1
STA. 1138+00.00	TO STA. 1144+00.00	LT		1
STA. 1144+00.00	TO STA. 1150+00.00	LT		1
STA. 1150+00.00	TO STA. 1156+00.00	LT		1
SUBTOTAL - URBAN				29
US RTE 30 - RURAL				
STA. 1162+00.00	TO STA. 1168+00.00	LT		1
STA. 1168+00.00	TO STA. 1174+30.00	LT		1
STA. 1168+00.00	TO STA. 1174+30.00	RT		2
SUBTOTAL - RURAL				4
TOTAL				33