

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
309	16R-2	WHITESIDE	547	21
STA.		TO STA.		
FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT				

PAY CODE		20100110	20100210
TREE REMOVAL SCHEDULE			
		TREE REMOVAL (6 TO 15 UNITS DIAMETER)	TREE REMOVAL (OVER 15 UNITS DIAMETER)
LOCATION		UNIT	UNIT
US RTE 30 - URBAN			
STA. 1115+21.14	34.53 FT	LT	18
STA. 1117+38.29	39.15 FT	LT	30
STA. 1125+86.02	49.86 FT	LT	36
STA. 1127+08.31	51.16 FT	RT	48
STA. 1127+14.06	72.94 FT	RT	8
STA. 1127+45.74	46.02 FT	RT	8
STA. 1128+27.98	45.42 FT	RT	8
STA. 1128+42.79	101.36 FT	LT	19
STA. 1128+43.79	89.70 FT	LT	15
STA. 1128+46.10	39.82 FT	LT	12
STA. 1128+49.86	55.26 FT	LT	8
STA. 1128+72.05	30.68 FT	LT	36
STA. 1128+99.87	44.76 FT	RT	8
STA. 1129+15.44	34.19 FT	LT	6
STA. 1129+48.68	29.20 FT	LT	12
STA. 1129+99.35	45.46 FT	LT	30
STA. 1130+13.17	31.94 FT	LT	6
STA. 1130+27.22	51.07 FT	LT	15
STA. 1130+30.73	58.78 FT	LT	18
STA. 1130+40.21	48.65 FT	LT	12
STA. 1130+40.30	50.79 FT	LT	15
STA. 1130+43.02	50.71 FT	LT	6
STA. 1130+46.10	59.73 FT	LT	15
STA. 1139+13.24	57.81 FT	LT	24
STA. 1139+50.09	46.18 FT	LT	15
STA. 1139+50.66	74.87 FT	LT	24
STA. 1139+68.48	66.39 FT	LT	24
STA. 1139+69.85	46.23 FT	LT	15
STA. 1140+19.49	42.33 FT	LT	12
STA. 1140+19.76	55.54 FT	LT	18
STA. 1149+24.09	51.90 FT	LT	15
STA. 1149+35.90	39.13 FT	LT	15
STA. 1149+55.62	39.81 FT	LT	6
STA. 1149+75.65	39.93 FT	LT	15
STA. 1149+86.46	43.47 FT	LT	24
STA. 1150+15.99	41.00 FT	LT	36
STA. 1150+43.30	40.08 FT	LT	36
STA. 1150+98.03	37.92 FT	LT	30
SAWYER ROAD			
STA. 8+52.47	31.62 FT	LT	6
STA. 8+78.90	31.04 FT	LT	8
STA. 9+09.55	41.36 FT	LT	27
BISHOP ROAD			
STA. 211+92.30	45.99 FT	RT	12
STA. 212+10.07	36.32 FT	RT	30
SUBTOTAL - URBAN		273	508
US RTE 30 - RURAL			
STA. 1158+10.00	85.00 FT	RT	9
STA. 1158+13.00	55.00 FT	RT	10
STA. 1158+15.00	73.00 FT	RT	6
STA. 1158+15.00	85.00 FT	RT	19
STA. 1158+18.00	55.00 FT	RT	10
STA. 1158+20.00	85.00 FT	RT	8
STA. 1158+25.00	55.00 FT	RT	13
STA. 1158+27.00	45.00 FT	RT	6
STA. 1158+30.00	50.00 FT	RT	15
STA. 1159+03.00	65.00 FT	RT	6
STA. 1159+20.00	65.00 FT	RT	6
STA. 1168+63.63	44.10 FT	RT	6
STA. 1168+99.07	44.66 FT	RT	6
STA. 1169+35.90	45.84 FT	RT	6
STA. 1169+70.96	50.25 FT	RT	30
SUBTOTAL - RURAL		107	49
TOTAL		380	557

PAY CODE		44000500	
COMBINATION CONCRETE CURB AND GUTTER REMOVAL SCHEDULE			
		COMBINATION CURB AND GUTTER REMOVAL	
LOCATION		FOOT	
US RTE 30 - URBAN			
STA. 1113+50.00	TO	STA. 1114+00.00	RT 50.00
STA. 1114+00.00	TO	STA. 1115+15.00	RT 115.00
STA. 1114+00.00	TO	STA. 1115+15.00	LT 115.00
STA. 1115+15.00	TO	STA. 1120+00.00	RT 485.21
STA. 1115+15.00	TO	STA. 1120+00.00	LT 485.05
STA. 1120+00.00	TO	STA. 1125+08.03	RT 408.08
STA. 1120+00.00	TO	STA. 1124+05.75	LT 405.75
STA. 1125+00.20	TO	STA. 1126+00.00	LT 100.02
STA. 1126+00.00	TO	STA. 1127+12.50	LT 112.47
STA. 1127+67.60	TO	STA. 1131+54.96	LT 388.07
SCENIC STREET			
STA. 15+22.76	TO	STA. 16+00.00	LT 78.66
STA. 15+23.81	TO	STA. 16+27.15	RT 108.03
SYCAMORE STREET			
STA. 5+30.17	TO	STA. 6+00.00	RT 70.50
STA. 5+30.66	TO	STA. 6+00.00	LT 70.16
SUBTOTAL - URBAN		2,992	
TOTAL		2,992	

PAY CODE		44000200	
DRIVEWAY PAVEMENT REMOVAL SCHEDULE			
		DRIVEWAY PAVEMENT REMOVAL	
LOCATION		SQ YD	
US RTE 30 - URBAN			
STA. 1113+70.83	TO	STA. 1114+00.00	RT 2.61
STA. 1114+00.00	TO	STA. 1114+35.83	RT 6.08
STA. 1114+28.26	TO	STA. 1114+67.10	LT 5.17
STA. 1114+75.76	TO	STA. 1115+14.60	LT 10.00
STA. 1116+24.21	TO	STA. 1118+62.18	RT 64.03
STA. 1118+21.26	TO	STA. 1118+55.86	LT 49.60
STA. 1122+97.91	TO	STA. 1123+45.86	RT 83.66
STA. 1126+78.01	TO	STA. 1127+08.11	RT 122.60
STA. 1135+11.51	TO	STA. 1136+85.65	RT 342.02
STA. 1149+78.23	TO	STA. 1150+64.44	RT 269.95
SAWYER ROAD			
STA. 8+32.61	TO	STA. 8+80.24	RT 130.05
SUBTOTAL - URBAN		1,086	
TOTAL		1,086	

PAY CODE		X0324056	
REMOVAL OF EXISTING WOOD BOLLARDS SCHEDULE			
		REMOVAL OF EXISTING WOOD BOLLARDS	
LOCATION		EACH	
SAWYER ROAD			
STA. 8+18.05	17.18 FT	RT	1
STA. 8+25.57	13.44 FT	RT	1
STA. 8+28.87	12.88 FT	RT	1
STA. 8+32.77	15.40 FT	RT	1
STA. 8+35.08	18.12 FT	RT	1
STA. 8+36.07	24.85 FT	RT	1
STA. 8+72.15	20.35 FT	RT	1
STA. 8+75.68	17.01 FT	RT	1
STA. 8+79.40	14.93 FT	RT	1
STA. 8+84.27	14.24 FT	RT	1
STA. 8+89.19	13.73 FT	RT	1
STA. 8+93.83	14.05 FT	RT	1
STA. 8+97.97	14.10 FT	RT	1
STA. 9+01.96	14.44 FT	RT	1
STA. 9+06.13	14.33 FT	RT	1
STA. 9+11.12	14.57 FT	RT	1
STA. 9+13.75	15.16 FT	RT	1
STA. 9+18.32	16.53 FT	RT	1
SUBTOTAL - URBAN		18	
TOTAL		18	

PAY CODE		44000100	44004250
PAVEMENT REMOVAL SCHEDULE			
		PAVEMENT REMOVAL	PAVED SHOULDER REMOVAL
LOCATION		SQ YD	SQ YD
US RTE 30 - URBAN			
STA. 1113+50.00	TO	STA. 1114+00.00	8.16
STA. 1114+00.00	TO	STA. 1115+15.00	80.75
STA. 1114+00.00	TO	STA. 1115+15.00	25.74
STA. 1115+15.00	TO	STA. 1120+00.00	1,287.44
STA. 1115+15.00 RT.	TO	STA. 1120+00.00 RT.	445.95
STA. 1115+15.00 LT.	TO	STA. 1120+00.00 LT.	532.07
STA. 1116+65.99	TO	STA. 1119+59.80	548.86
STA. 1120+00.00	TO	STA. 1126+00.00	1,621.37
STA. 1120+00.00 RT.	TO	STA. 1126+00.00 RT.	421.89
STA. 1120+00.00 LT.	TO	STA. 1124+30.82 LT.	280.96
STA. 1126+00.00	TO	STA. 1132+00.00	2,228.45
STA. 1126+00.00 RT.	TO	STA. 1126+17.51 RT.	9.04
STA. 1127+79.56	TO	STA. 1129+52.52	349.32
STA. 1132+00.00	TO	STA. 1138+00.00	1,673.18
STA. 1138+00.00	TO	STA. 1144+00.00	1,726.94
STA. 1144+00.00	TO	STA. 1150+00.00	1,685.20
STA. 1150+00.00	TO	STA. 1156+00.00	1,629.75
STA. 1150+72.36 RT	TO	STA. 1155+16.14 RT	366.29
SUBTOTAL - URBAN		13,232	1,690
US RTE 30 - RURAL			
STA. 1157+87.00	TO	STA. 1158+43.00	158.26
STA. 1166+48.39 RT	TO	STA. 1168+00.00 RT	70.74
STA. 1167+06.27 LT	TO	STA. 1168+00.00 LT	86.44
STA. 1168+00.00 RT	TO	STA. 1174+30.00 RT	548.63
STA. 1168+00.00 LT	TO	STA. 1174+30.00 LT	500.48
STA. 1168+00.00	TO	STA. 1174+30.00	1,715.46
SUBTOTAL - RURAL		1,874	1,207
TOTAL		15,106	2,897

PAY CODE		28000300	
TEMPORARY DITCHES			
TEMPORARY DITCH-CHECK SCHEDULE		TEMPORARY DITCH CHECKS	
LOCATION		LEFT	RIGHT
US RTE 30 - URBAN			
STA. 1120+50.00		1	
STA. 1121+50.00		1	
STA. 1123+00.00		1	
SUBTOTAL - URBAN		0	3
TOTAL - URBAN		3	
US RTE 30 - RURAL			
STA. 1171+00.00		1	
STA. 1172+00.00		1	
STA. 1173+00.00		1	
STA. 1174+00.00		1	
SUBTOTAL - RURAL		0	4
TOTAL - RURAL		4	
TOTAL		7	

NOTES:
 1. TEMPORARY DITCH CHECKS ARE SPACED EVERY 100', TYPICALLY
 2. SEE STD. 280001
 3. ADDITIONAL TEMPORARY DITCH CHECKS MAY BE REQUIRED AT LOCATIONS NOT SPECIFIED IN THE SCHEDULE AS DIRECTED BY THE RESIDENT ENGINEER.

PAY CODE		44000400	
GUTTER REMOVAL			
		GUTTER REMOVAL	
LOCATION		FOOT	
US RTE 30 - URBAN			
STA. 1136+96.25	TO	STA. 1138+00.00	LT 103.77
STA. 1138+00.00	TO	STA. 1139+95.84	LT 249.55
STA. 1140+05.49	TO	STA. 1140+99.97	LT 145.45
STA. 1147+76.90	TO	STA. 1148+78.22	LT 105.83
STA. 1149+26.76	TO	STA. 1150+00.00	LT 73.25
STA. 1150+00.00	TO	STA. 1153+06.48	LT 312.63
SUBTOTAL - URBAN		991	
TOTAL		991	

PAY CODE		44000600	
SIDEWALK REMOVAL SCHEDULE			
		SIDEWALK REMOVAL	
LOCATION		SQ FT	
US RTE 30 - URBAN			
STA. 1126+82.64	RT	TO	STA. 1126+90.16
			RT 12.02
SCENIC STREET			
STA. 15+62.52	RT	TO	STA. 15+67.00
			RT 13.43
SUBTOTAL - URBAN		26	
TOTAL		26	

PAY CODE		63200310	
GUARDRAIL REMOVAL SCHEDULE			
		GUARDRAIL REMOVAL	
LOCATION		FOOT	
US RTE 30 - URBAN			
STA. 1145+89.81	TO	STA. 1147+41.92	RT 152.11
STA. 1146+09.95	TO	STA. 1147+59.90	LT 149.95
SUBTOTAL - URBAN		303	
US RTE 30 - RURAL			
STA. 1157+20.72	TO	STA. 1158+84.44	RT 163.72
STA. 1157+47.05	TO	STA. 1159+09.00	LT 161.95
STA. 1167+85.49	TO	STA. 1171+00.88	RT 315.39
STA. 1168+52.63	TO	STA. 1172+18.48	LT 365.85
SUBTOTAL - RURAL		1,007	
TOTAL		1,310	

PAY CODE		*Z0007801	
BUILDING REMOVAL NO. 1 SCHEDULE			
		BUILDING REMOVAL NO. 1	
LOCATION		L SUM	
US RTE 30 - URBAN			
STA. 1128+85.08	LT	TO	STA. 1129+07.66
			LT 1
SUBTOTAL - URBAN		1	