CONTRACT NO. 64969

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
309	16R-2	WHITESIDE	547	27
STA.		TO STA.		
FED. ROAD DIST. NO. 2	ILLINOIS	FED. AID PROJECT		

CONCRETE CURB AND GUTTER SCHEDULE

LOCATION			LT/RT	CLASS SI CONCRETE (OUTLET)	CONCRETE GUTTER (SPECIAL)	GUTTER OUTLET (SPECIAL)	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	PROTECTIVE COAT
PAY CODE				60600095	60602400	60603400	X6063600	60603800	60604400	60605000	42001300
				CU YD	FOOT	EACH	FOOT	FOOT	FOOT	FOOT	SQ YD
US RTE 30 - URBAN											
STA. 1113+50.00	TO	STA. 1114+00.00	RT							50.00	33.41
STA. 1114+00.00	TO	STA. 1115+15.00	RT							115.00	76.84
STA. 1114+00.00	TO	STA. 1115+15.00	LT							115.00	76.84
STA. 1115+15.00	TO	STA. 1120+00.00	LT							484.96	324.05
STA. 1115+15.00	TO	STA. 1120+00.00	RT							485.20	324.21
STA. 1120+00.00	TO	STA. 1126+00.00	LT							599.82	400.80
STA. 1120+00.00	TO	STA. 1126+00.00	RT							600.18	401.04
STA. 1126+00.00	TO	STA. 1127+19.60	LT							129.16	86.30
STA. 1126+00.00	TO	STA. 1129+70.75	RT							403.24	269.44
STA. 1127+60.26	TO	STA. 1130+83.88	LT							341.16	227.96
STA. 1127+86.13			LT			1					
STA. 1127+90.75	TO	STA. 1130+75.26	LT		287.46						
STA. 1128+20.00	TO	STA. 1129+29.25	RT					136.46			60.86
STA. 1130+09.37	TO	STA. 1132+00.00	RT							231.69	154.82
STA. 1130+75.61			LT			1					
STA. 1131+25.20	TO	STA. 1132+00.00	LT							83.48	55.78
STA. 1131+67.05			LT			1					
STA. 1131+71.68	TO	STA. 1133+44.95	LT		173.34						
STA. 1132+00.00	TO	STA. 1133+48.57	RT							148.53	99.25
STA. 1132+00.00	TO	STA. 1133+48.57	LT							148.61	99.30
STA. 1133+48.57			LT	1.23							8.96
STA. 1133+48.57			RT	1.23							8.96
STA. 1133+49.57			LT			1					
STA. 1147+78.64	TO	STA. 1148+35.27	LT	4.58							24.01*2
STA. 1148+35.27	TO	STA. 1150+00.00	LT				164.83				113.62
STA. 1150+00.00	TO	STA. 1152+71.64	LT				271.70				187.29
STA. 1152+71.64	TO	STA. 1153+11.63	LT	3.44							35.20
SCENIC STREET											
STA. 15+50.28	TO	STA. 16+00.00	LT						49.89		27.79
STA. 15+50.28	TO	STA. 16+29.17	RT						80.34		44.76
SYCAMORE STREET											
STA. 5+49.22	TO	STA. 6+00.00	LT						51.06		28.44
STA. 5+49.22	TO	STA. 6+00.00	RT						51.06		28.44
SAWYER ROAD											
STA. 7+44.10	TO	STA. 7+98.98	LT	3.82							41.26
STA. 7+67.33	TO	STA. 8+22.20	RT	3.82							41.22
STA. 7+98.98	TO	STA. 8+97.50	LT							99.20	66.29
STA. 8+22.20	TO	STA. 8+97.50	RT							75.30	50.32
SUBTOTAL - URBAN				**18.2**	**461.0**	**4**	**437.0**	**136.5**	**232.5**	**4,111.0**	**3,374.0**
TOTAL				**18.2**	**461.0**	**4**	**437.0**	**136.5**	**232.5**	**4,111.0**	**3,374.0**

NOTE:
PROTECTIVE COAT SHALL BE PROVIDED ON COMB. CONC. CURB AND GUTTER AND P.C.C. PAVEMENT IF CONSTRUCTED AFTER OCT. 15TH AND TRAFFIC IS ANTICIPATED PRIOR TO THE FOLLOWING APRIL 15TH.

PERMANENT PAVEMENT MARKING SCHEDULE

LOCATION			*78003110 PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4" WHITE	*78008200 POLYUREA PAVEMENT MARKING TYPE 1 - LETTERS AND SYMBOLS	*78008210 POLYUREA PAVEMENT MARKING TYPE I - LINE 4" **WHITE	YELLOW	DBL. YEL.	YEL. SKIP	*78008240 POLYUREA PAVEMENT MARKING TYPE I - LINE 8" WHITE	*78008250 POLYUREA PAVEMENT MARKING TYPE I - LINE 12" YELL. DIAG.	*78008270 POLYUREA PAVEMENT MARKING TYPE I - LINE 24" WHITE
			FOOT	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
US RTE 30 - URBAN											
STA. 1108+81.68	TO	STA. 1114+00.00	670.76	31.2		476.64	560.00	119.16			
STA. 1114+00.00	TO	STA. 1120+00.00	1,200.42	78.0		1,200.00		300.00			
STA. 1120+00.00	TO	STA. 1126+00.00	1,200.02	78.0		1,189.03	10.98	297.26			
STA. 1126+00.00	TO	STA. 1132+00.00	1,233.25	124.8	519.56	114.54	859.54	28.64	393.55	48.56	
STA. 1132+00.00	TO	STA. 1138+00.00	1,202.13			130.03	1,941.24		13.57	201.23	
STA. 1138+00.00	TO	STA. 1144+00.00	1,200.00				1,200.00				
STA. 1144+00.00	TO	STA. 1150+00.00	1,202.07			75.90	1,404.28			28.59	
STA. 1150+00.00	TO	STA. 1156+00.00	1,201.70	62.4	77.99	114.07	1,696.86		237.97	119.19	
STA. 1156+00.00	TO	STA. 1157+00.00	241.21		112.83		4.04		2.02		
SCENIC STREET											
STA. 15+37.54	TO	STA. 16+00.00	99.45				147.92				27.65
SAWYER ROAD											
STA. 7+00.00	TO	STA. 9+50.60	395.67		74.25		183.20				39.44
SYCAMORE STREET											
STA. 5+37.53	TO	STA. 6+00.00	101.56				147.94				28.28
BISHOP ROAD											
STA. 210+46.02	TO	STA. 212+31.00	274.40			72.30	505.98			30.01	32.36
SUBTOTAL - URBAN			**10,223**	**375**	**785**	**3373**	**8662**	**746**	**648**	**428**	**128**
TOTAL - URBAN			**10,223**	**375**	**13,566**				**648**	**428**	**128**
US RTE 30 - RURAL											
STA. 1157+00.00	TO	STA. 1162+00.00	1,001.26	62.4	26.53		1,988.44		260.79	251.76	
STA. 1162+00.00	TO	STA. 1168+00.00	1,202.13			267.54	1,282.54	50.00		91.33	
STA. 1168+00.00	TO	STA. 1174+30.00	1,260.00			300.00		157.50			
STA. 1174+30.00	TO	STA. 1178+30.00	800.00					100.00			
SUBTOTAL - RURAL			**4,264**	**63**	**27**	**568**	**3271**	**308**	**261**	**344**	**0**
TOTAL - RURAL			**4,264**	**63**	**4,174**				**261**	**344**	**0**
TOTAL			**14,487**	**438**	**17,740**				**909**	**772**	**128**

** IF CONTRACTOR IS UNABLE TO INLAY PREFORMED PLASTIC PAVEMENT MARKING AROUND RADII AT SIDEROADS.

WORK ZONE PUBLIC INFO SIGN SCHEDULE

LOCATION	PAY CODE X7200400 WORK ZONE PUBLIC INFORMATION SIGNS EACH
US RTE 30 - URBAN	
ENTIRE PROJECT	2
SUBTOTAL - URBAN	**2**
US RTE 30 - RURAL	
ENTIRE PROJECT	2
SUBTOTAL - RURAL	**2**
TOTAL	**4**

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
FAP ROUTE 309 (US 30)
SECTION 16R-2, EAST CONTRACT
FROM 0.2 MILE EAST OF JACKSON ST.
TO FRENCH CREEK
WHITESIDE COUNTY

SCALE: N.T.S. DRAWN BY CAM
DATE 09/01/05 CHECKED BY RDY