CONTRACT NO. 64969

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
309	16R-2	WHITESIDE	547	30
STA.		TO STA.		
FED. ROAD DIST. NO. 2	ILLINOIS FED. AID PROJECT			

PAY CODE							20800150	XX001135	54213657	54213660	54213663	54213675	54247150	60218400	60218500	60221700	60223800	60236200	60242801	60242802	550A0140	550A0340	550A0360	550A0380	550A0400	550A0410
STORM SEWER SCHEDULE (CONTINUED)							TRENCH BACKFILL	PAVEMENT PATCHING SPECIAL	PRECAST REINFORCED CONCRETE FLARED END SECTIONS				GRATING FOR CONCRETE FLARED END SECTION 30"	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	INLETS, TYPE A, TYPE 8 GRATE	INLETS, SPECIAL, NO. 5	INLETS, SPECIAL, NO. 6	STORM SEWERS, CLASS A, TYPE 1	STORM SEWERS, CLASS A, TYPE 2				
									12"	15"	18"	30"									30"	12"	15"	18"	21"	24"
LOCATION							CU YD	SQ YD	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	FT	FT	FT	FT	FT	FT
STA. 1134+76.60	47.00 FT	RT							1																	
STA. 1133+49.57	38.08 FT	LT																1								
STA. 1133+75.00	38.08 FT	LT							1																	
SCENIC STREET																										
STA. 15+60.00	18.00 FT	LT																	1							
STA. 15+65.00	18.00 FT	RT																	1							
STA. 15+65.00	18.00 FT	RT	TO	STA. 15+60.00	18.00 FT	LT	6.0																			
SAWYER ROAD																										
STA. 8+76.00	24.00 FT	LT												1												
STA. 9+00.00	35.90 FT	RT														1										
STA. 7+68.10	24.00 FT	RT									1															
STA. 8+76.00	24.00 FT	LT	TO	STA. 7+40.00	22.50 FT	LT	161.6																132			
STA. 9+00.00	35.90 FT	RT	TO	STA. 7+68.10	24.00 FT	RT	118.0																	133		
STA. 7+40.00	22.50 FT	LT								1																
SYCAMORE STREET																										
STA. 5+45.00	23.00 FT	RT																	1							
STA. 5+45.00	22.00 FT	LT																	1							
STA. 5+45.00	22.00 FT	LT	TO	STA. 5+45.00	23.00 FT	RT	6.2	16																		
SUBTOTAL - URBAN							1,620	220	2	1	1	1	1	6	1	1	2	5	21	1	2	609	616	504	183	207
TOTAL							1,620	220	2	1	1	1	1	6	1	1	2	5	21	1	2	609	616	504	183	207

PAY CODE							*550A2520	*550A2580	X0322033	Z0065767
STORM SEWER SCHEDULE (CONTINUED)							STORM SEWER, RUBBER GASKET, CLASS A, TYPE 2		STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	SLOTTED DRAIN 15" WITH 1 3/4" SLOT
							12"	30"		
LOCATION							FT	FT	FT	FT
US RTE 30 - URBAN										
STA. 1115+75.21	26.50 FT	LT								
STA. 1115+74.94	26.10 FT	RT								
STA. 1115+75.21	26.50 FT	LT	TO	STA. 1115+74.94	26.10 FT	RT	54			
STA. 1115+74.94	26.10 FT	RT	TO	STA. 1114+38.75	23.30 FT	RT				
STA. 1120+60.00	28.00 FT	RT								
STA. 1120+60.00	28.00 FT	LT								
STA. 1122+35.00	28.00 FT	LT								
STA. 1122+35.00	28.00 FT	RT								
STA. 1123+92.27	29.84 FT	LT								
STA. 1123+91.21	40.43 FT	LT								
STA. 1123+96.83	30.00 FT	RT								
STA. 1123+75.09	28.00 FT	RT								
STA. 1124+80.00	28.00 FT	RT								
STA. 1124+58.00	28.00 FT	LT								
STA. 1126+96.33	36.55 FT	LT								
STA. 1120+60.00	28.00 FT	RT	TO	STA. 1120+60.00	28.00 FT	LT	57			
STA. 1120+60.00	28.00 FT	LT	TO	STA. 1122+35.00	28.00 FT	LT				
STA. 1122+35.00	28.00 FT	RT	TO	STA. 1122+35.00	28.00 FT	LT	57			
STA. 1122+35.00	28.00 FT	LT	TO	STA. 1123+92.27	29.84 FT	LT				
STA. 1123+92.27	29.84 FT	LT	TO	STA. 1123+91.21	40.43 FT	LT				
STA. 1123+92.27	29.84 FT	LT	TO	STA. 1123+96.83	30.00 FT	RT		56		
STA. 1123+75.09	28.00 FT	RT	TO	STA. 1123+96.83	30.00 FT	RT			17	
STA. 1124+80.00	28.00 FT	RT	TO	STA. 1123+96.83	30.00 FT	RT			78	
STA. 1124+58.00	28.00 FT	LT	TO	STA. 1123+92.27	29.84 FT	LT				
STA. 1126+10.03	28.00 FT	LT	TO	STA. 1124+58.00	28.00 FT	LT				
STA. 1126+10.06	28.00 FT	RT								
STA. 1126+10.03	28.00 FT	LT								
STA. 1126+88.85	28.00 FT	LT								
STA. 1127+86.13	38.08 FT	LT								
STA. 1127+86.13	38.08 FT	LT	TO	STA. 1127+90.75	28.00 FT	LT				
STA. 1127+90.75	28.00 FT	LT								
STA. 1126+10.06	28.00 FT	RT	TO	STA. 1126+10.06	28.00 FT	LT	57			
STA. 1126+88.85	28.00 FT	LT	TO	STA. 1126+10.03	28.00 FT	LT				
STA. 15+60.00	18.00 FT	LT	TO	STA. 1126+96.33	36.55 FT	LT				
STA. 1126+96.33	36.55 FT	LT	TO	STA. 1126+88.85	28.00 FT	LT				
STA. 1127+74.60	26.00 FT	LT	TO	STA. 1126+88.85	28.00 FT	LT				86.0
STA. 1127+90.75	28.00 FT	LT	TO	STA. 1128+60.18	28.00 FT	LT				
STA. 1128+60.18	28.00 FT	LT								
STA. 1128+60.09	35.00 FT	RT								
STA. 1128+75.00	48.15 FT	RT								
STA. 1129+18.50	48.25 FT	RT								
STA. 1130+20.14	49.60 FT	RT								
STA. 1126+96.33	36.55 FT	LT	TO	STA. 1127+90.75	28.00 FT	LT				
STA. 1128+75.00	48.15 FT	RT	TO	STA. 1129+18.50	48.25 FT	RT				
STA. 1129+18.50	48.25 FT	RT	TO	STA. 8+76.00	24.00 FT	LT				

PAY CODE							*550A2520	*550A2580	X0322033	Z0065767
STORM SEWER SCHEDULE (CONTINUED)							STORM SEWER, RUBBER GASKET, CLASS A, TYPE 2		STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	SLOTTED DRAIN 15" WITH 1 3/4" SLOT
							12"	30"		
LOCATION							FT	FT	FT	FT
STA. 9+00.00	35.90 FT	RT	TO	STA. 1130+45.35	42.05 FT	RT				
STA. 1130+20.14	49.60 FT	RT	TO	STA. 1130+45.35	42.05 FT	RT				
STA. 1130+45.35	42.05 FT	RT	TO	STA. 1131+55.78	39.80 FT	RT				
STA. 1131+55.78	39.80 FT	RT	TO	STA. 1132+49.90	42.75 FT	RT				
STA. 1130+53.65	28.00 FT	LT	TO	STA. 1131+55.41	28.00 FT	LT				
STA. 1131+67.05	38.08 FT	LT	TO	STA. 1131+55.41	28.00 FT	LT				
STA. 1130+53.65	28.00 FT	LT	TO	STA. 5+45.00	22.00 FT	LT			30	
STA. 1130+75.61	52.81 FT	LT	TO	STA. 5+45.00	22.00 FT	LT				
STA.1130+53.65	28.00 FT	LT	TO	STA. 1131+39.00	26.00 FT	LT				86.0
STA. 1130+75.61	52.81 FT	LT								
STA. 1130+45.35	42.05 FT	RT								
STA. 1131+55.78	39.80 FT	RT								
STA. 1131+55.41	28.00 FT	LT								
STA. 1131+67.05	38.08 FT	LT								
STA. 1132+49.90	42.75 FT	RT	TO	STA. 1132+49.90	51.65 FT	RT				
STA. 1132+49.90	42.75 FT	RT	TO	STA. 1134+76.60	47.00 FT	RT				
STA. 1130+45.35	42.05 FT	RT	TO	STA. 1130+53.65	28.00 FT	LT				
STA. 1128+60.09	35.00 FT	RT	TO	STA. 1128+75.00	48.15 FT	RT				
STA. 1133+49.57	38.08 FT	LT	TO	STA. 1133+75.00	38.08 FT	LT				
STA.1130+53.65	28.00 FT	LT								
STA. 1132+49.90	42.75 FT	RT								
STA. 1132+49.90	51.65 FT	RT								
STA. 1134+76.60	47.00 FT	RT								
STA. 1133+49.57	38.08 FT	LT								
STA. 1133+75.00	38.08 FT	LT								
SCENIC STREET										
STA. 15+60.00	18.00 FT	LT								
STA. 15+65.00	18.00 FT	RT								
STA. 15+65.00	18.00 FT	RT	TO	STA. 15+60.00	18.00 FT	LT	37			
SAWYER ROAD										
STA. 8+76.00	24.00 FT	LT								
STA. 9+00.00	35.90 FT	RT								
STA. 7+68.10	24.00 FT	RT								
STA. 8+76.00	24.00 FT	LT	TO	STA. 7+40.00	22.50 FT	LT				
STA. 9+00.00	35.90 FT	RT	TO	STA. 7+68.10	24.00 FT	RT				
STA. 7+40.00	22.50 FT	LT								
SYCAMORE STREET										
STA. 5+45.00	23.00 FT	RT								
STA. 5+45.00	22.00 FT	LT								
STA. 5+45.00	22.00 FT	LT	TO	STA. 5+45.00	23.00 FT	RT			47	
SUBTOTAL - URBAN							262	56	172	172
TOTAL							262	56	172	172

PAY CODE	72000100	72800100	*78000200
MORRISON CLINIC SITE SCHEDULE			
	SIGN PANEL - TYPE 1	TELESCOPING STEEL SIGN SUPPORT	THERMOPLASTIC PAVEMENT MARKING - LINE 4"
LOCATION	SQ FT	FOOT	FOOT
CLINIC SITE	2	13	185
SUBTOTAL - URBAN	2	13	185
TOTAL	2	13	185

PAY CODE	20800150
TRENCH BACKFILL SCHEDULE	
	TRENCH BACKFILL
LOCATION	CU YD
US RTE 30 - RURAL	
STA. 1158+14.82	125.16
SUBTOTAL - RURAL	126
TOTAL	126

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
FAP ROUTE 309 (US 30)
SECTION 16R-2, EAST CONTRACT
FROM 0.2 MILE EAST OF JACKSON ST.
TO FRENCH CREEK
WHITESIDE COUNTY

SCALE: N.T.S. DRAWN BY CAM

DATE 09/01/05 CHECKED BY RDY