

SUMMARY OF QUANTITIES

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
227	105BR-2	HENRY	31	2
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	X080-2A 80 % FED 20 % STATE	SFTY-3N 80 % FED 20 % STATE
44000007	BITUMINOUS SURFACE REMOVAL 2"	SQ YD	142	142	
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	1	
50300260	BRIDGE DECK GROOVING	SQ YD	262	262	
50300300	PROTECTIVE COAT	SQ YD	295	295	
5030305	CONCRETE WEARING SURFACE 5"	SQ YD	280	280	
50301245	FORMED CONCRETE REPAIR, (DEPTH EQUAL TO OR LESS THAN 5")	SQ FT	126	126	
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ. FT.	2518	2518	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	785	785	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3810	3810	
50901005	STEEL BRIDGE RAIL, TYPE SM	FOOT	151	151	
51401600	TEMPORARY BRIDGE RAIL	FOOT	77	77	
51500100	NAME PLATES	EACH	1	1	
59000100	EPOXY CRACK SEALING	FOOT	56	56	
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	2	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3	
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION STD 701321	EACH	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION STD. 701201	L SUM	1	1	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1634	1634	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	800	800	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	460	460	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	380	380	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2400	2400	
X0322932	SILICONE JOINT SEALER, 1.5"	FOOT	77	77	
X4066414	BITUMINOUS CONCRETE SURFACE COARSE, SUPERPAVE, MIX 'C', N50	TON	20	20	
X0712400	TEMPORARY PAVEMENT	SQ YD	80	80	
* XX005496	TRAFFIC BARRIER TERMINAL, TYPE 6A (SPECIAL)	EACH	4	4	
* Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	24	24	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2		2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2		2

* SPECIALTY ITEMS

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. HORIZ. DATE DRAWN BY CHECKED BY