CONTRACT NO. 64B25

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
227	105BR-2	HENRY	31	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCHEDULE OF QUANTITIES

44000007 BITUMINOUS CONCRETE SURFACE REMOVAL 2"

SQ YD	LOCATION				
71	64+	88-	65+	7.9	LT & RT
71	65+	86-	66+	6.4	LT & RT
142	TOTAL				

50101500 REMOVAL OF EXISTING SUPERSTRUCTURES

EACH	LOCATION
1	
1	TOTAL

50901005 STEEL BRIDGE RAIL, TYPE SM

FOOT	LOCATION				
92	64+	92-	65+	83	RT
92	65+	11-	66+	2.3	LT
184	TOTAL				

63301210 TEMPORARY CONCRETE BARRIER

FOOT	LOCATION				
190	63+	19-	65+	8.6	STAGE 1
190	65+	88-	67+	78	STAGE 1
80	65+	8.6-	65+	88	STAGE 2
460	TOTAL				

70300100 SHORT TERM PAVEMENTMARKING

FOOT	LOCATION				
817	61+	40-	69+	57	STAGE 1
817	61+	40-	69+	57	STAGE 2
1634	TOTAL				

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

SQ FT	LOCATION				
400	61+	40-	69+	57	STAGE 1
400	61+	40-	69+	57	STAGE 2
800	TOTAL				

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

FOOT	LOCATION				
190	63+	19-	65+	8.6	LT & RT
190	65+	88-	67+	78	LT & RT
380	TOTAL				

78001110 PAINT PAVEMENT MARKING LINE 4"

FOOT	LOCATION				
1000	62+	50 -	67+	50	WHITE EDGELINES - 2 COATS
1000	63+	25 -	68+	25	WHITE EDGELINES - 2 COATS
400	61+	60 -	69+	40	SKIP DASH YELLOW - 2 COATS
2400	TOTAL				

X0712400 TEMPORARY PAVEMENT

SQ YD	LOCATION				
40	62+	57 -	63+	77	LT
40	67+	16 -	68+	36	RT
80	TOTAL				

X4066414 BITUMINOUS CONCRETE SURFACE COARSE, SUPERPAVE, MIX C, N50

TON	LOCATION				
10	64+	88-	65+	7.9	LT & RT
10	65+	86-	66+	6.4	LT & RT
20	TOTAL				

XX005496 TRAFFIC BARRIER TERMINAL, TYPE 6A (SPECIAL)

EACH	LOCATION				
1	64+	58-	64+	92	RT
1	64+	77-	65+	11	LT
1	65+	83-	66+	17	RT
1	66+	2.3-	66+	36	LT
4	TOTAL				

Z0030250 IMPACT ATENUATORS, TEMPORARY (NON -RE-DIRECTIVE), TEST LEVEL 3

EACH	LOCATION		
1	63+	19	RT
1	67+	78	RT
2	TOTAL		

Z0030350 IMPACT ATTENUATORS, RELOCATE (NON -RE-DIRECTIVE), TEST LEVEL 3

EACH	LOCATION		
1	63+	16	LT
1	67+	75	LT
2	TOTAL		

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = Mon Dec 19 09:54:16 2005
FILE NAME = c:\pw_pw1\projects\p2888985\d888985sv1.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = garfj1