

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
627	1BR	LASALLE	69	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

LOCATION	PAVEMENT MARKING				
	EPOXY			RAISED REFL PAVT MARK BRIDGE	RAISED REFL PAVEMENT MARKERS
	4"	4"	6"		
	WHITE FOOT	YELLOW FOOT	YELLOW FOOT	EACH	EACH
STA. 17+03 - STA. 17+93					
EDGE LINE	180				
NO PASSING ZONE		180			2
STA. 17+93 - STA. 24+54					
NO PASSING ZONE		661			
EDGE LINE	1322				
CENTERLINE			740		9
STA. 24+54 - STA. 28+69					
NO PASSING ZONE		415			
EDGE LINE	830				
CENTERLINE			110	5	
STA. 28+69 - STA. 30+65					
EDGE LINE	392				
CENTERLINE			50		3
TOTALS	2724	1256	900	5	14

LOCATION QUADRANT	GUARD RAIL REMOV FOOT	TRAF BAR TERM		SPBGR TYPE A FOOT	SPBGR TYPE A FOOT
		TYPE 6 EACH	TYPE 1 SPEC (TANG) EACH		
NORTHWEST	96	1		275	8.1
SOUTHWEST	96	1	1	225	
NORTHEAST	108	1		87.5	13.6
SOUTHEAST	108	1		87.5	13.6
TOTALS	408	4	1	675	35.3

LOCATION	TEMPORARY EROSION CONTROL		
	TEMP DITCH CHECKS EACH	PER EROS BARR FOOT	TEMP EROS CONT SEEDING POUND
	NORTHWEST QUADRANT	6	285
SOUTHWEST QUADRANT	6	305	116
NORTHEAST QUADRANT		315	32
SOUTHEAST QUADRANT		165	32
TOTAL	12	1070	320

LOCATION	SIDE	TYPE	BIT SURF REM BUTT JT SQ YD	BIT MATLS PRIME COAT GALLON	INC BIT SURF SUPER TON			
			STA. 18+52.02	RT	SR	11	8.5	11.8
			STA. 19+00	LT	CE	29	6.2	8.5
STA. 20+86 - STA. 21+70	RT	MBTO/PE	15	6.8	9.5			
TOTALS			55	22	30			

PLOT DATE = 10/31/2005
 PLOT SCALE = 1"=100'
 USER NAME = RUSERR

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
**SCHEDULE OF
 QUANTITIES**
 SCALE: VERT.
 DATE: HORIZ.
 DRAWN BY
 CHECKED BY