

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1488	(16,17,18)RS	MCLEAN	6	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

PAVEMENT MARKING SCHEDULE							
LOCATION	PAINT PVMT MRK - LINE 4" (WHITE)	PAINT PVMT MRK - LINE 4" (YELLOW)	PAINT PVMT MRK - LINE 6" (YELLOW)	RAISED REFLECTIVE PVMT MARKER	RAISED REFLECTIVE PVMT MARKER REMOVAL	SHORT TERM PVMT MRK	WORK ZONE PVMT MRK REMOVAL
LOG MILE	FT	FT	FT	EACH	EACH	FT	SQ FT
0.00 TO 4.49	47,415	3,960	5,927	296	296	2,370	790
4.51 TO 8.61	43,402	3,960	5,426	272	272	2,170	723
TOTAL	90,817	7,920	11,353	568	568	4,540	1,513

NOTE: THE ENGINEER SHALL VERIFY THE LOCATION OF THE NO PASSING ZONES PRIOR TO CONSTRUCTION

MICROSURFACING, 1-PASS	
LOCATION	MICROSURFACING
LOG MILE	SQ YD
0.00 TO 4.49	63,220
4.51 TO 8.61	57,728
TOTAL	120,948

GAP SN 057-0003

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. HORIZ. DATE

DRAWN BY CHECKED BY