

SUMMARY OF QUANTITIES

URBAN  
80% FEDERAL  
20% STATE  
0% CITY

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5952	G-BR-1	GRUNDY	50	5
STA.		TO STA.		
FED. ROAD DIST. NO. 7		ILLINOIS FED. AID PROJECT		

CODE NO	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	EAST FORK NETTLE CR. PR. 032-0108 EX. 032-0081
50200100	STRUCTURE EXCAVATION	CU YD	177	X020-2A	X020-2A
50300100	FLOOR DRAINS	EACH	8		8
50300225	CONCRETE STRUCTURES	CU YD	270.7		270.7
50300255	CONCRETE SUPERSTRUCTURE	CU YD	422.5		422.5
50300260	BRIDGE DECK GROOVING	SQ YD	632		632
50300300	PROTECTIVE COAT	SQ YD	1423	568	855
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	102250		102250
50900105	ALUMINUM RAILING, TYPE L	FOOT	211		211
51201400	FURNISHING STEEL PILES HP10X42	FOOT	1630		1630
51202700	DRIVING STEEL PILES	FOOT	1630		1630
51203400	TEST PILE STEEL HP10X42	EACH	2		2
51205200	TEMPORARY SHEET PILING	SQ FT	250		250
51401600	TEMPORARY BRIDGE RAIL	FOOT	231		231
51500100	NAME PLATES	EACH	1		1
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1	1	
54213672	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 27"	EACH	1	1	
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1	1	
55100200	STORM SEWER REMOVAL 6"	FOOT	83	83	
55100500	STORM SEWER REMOVAL 12"	FOOT	43	43	
55101200	STORM SEWER REMOVAL 24"	FOOT	31	31	
55101300	STORM SEWER REMOVAL 27"	FOOT	172	172	
55101400	STORM SEWER REMOVAL 30"	FOOT	123	123	
60213800	RESTRICTED DEPTH CATCH BASINS, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1	
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3	
60221200	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	1	1	
60225400	RESTRICTED DEPTH MANHOLES, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2	
60225500	RESTRICTED DEPTH MANHOLES, 5'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	1	1	
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	3	3	
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	3	3	
60255500	MANHOLES TO BE ADJUSTED	EACH	2	2	
60500040	REMOVING MANHOLES	EACH	3	3	
60500060	REMOVING INLETS	EACH	3	3	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	843	843	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7	7	
67100100	MOBILIZATION	L SUM	1	1	

11/7/2005 3:17:50 PM n:\54\cond\66563\66563\_Ext\Fork\54\66563.dgn

BOWMAN, BARRETT & ASSOCIATES INC.  
CONSULTING ENGINEERS  
130 E. RANDOLPH STREET  
CHICAGO, ILLINOIS 60601  
JOB NO. 541



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
  
U.S. ROUTE 6  
SUMMARY OF QUANTITIES  
  
SCALE: VERT. NTS  
HORIZ. NTS  
DATE 10/25/05  
  
DRAWN BY RGR  
CHECKED BY DDM