CONTRACT NO. 66563

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5952	G-BR-1	GRUNDY	50	7
STA.		TO STA.		
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

				URBAN 80% FEDERAL 20% STATE 0% CITY	
				ROADWAY	EAST FORK NETTLE CR. PR. 032-0108 EX. 032-0081
CODE NO	ITEM	UNIT	TOTAL QUANTITY	X020-2A	X020-2A
550A2570	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 27"	FOOT	57	57	
X0321430	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC) SPECIAL	SQ YD	110	110	
* X0322033	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	13	13	
* X0322089	STORM SEWER (WATER MAIN REQUIREMENTS) 36 INCH	FOOT	82	82	
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	1	1	
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	5	5	
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	181	181	
X4066616	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70	TON	528	528	
X4066770	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	TON	407	407	
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION, LOCATION 1	EACH	1		1
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION, LOCATION 2	EACH	1		1
XX003455	POROUS GRANULAR EMBANKMENT, SUBGRADE	TON	297	297	
Z0002600	BAR SPLICERS	EACH	438		438
Z0013825	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	799	799	
⊙ Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2	
⊙ Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2	

⊙ SFTY-3N

m:\541\cadd\civil\66563 East Fork\54scsd0_EF.dgn 8/2/2005 3:38:35 PM

default

BOWMAN, BARRETT & ASSOCIATES INC.
CONSULTING ENGINEERS
130 E. RANDOLPH STREET
CHICAGO, ILLINOIS 60601
JOB NO. 541

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

U.S. ROUTE 6
SUMMARY OF QUANTITIES

SCALE: VERT. NTS
HORIZ. NTS
DATE 10/25/05

DRAWN BY RGR
CHECKED BY DDM