

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
681	113BR-2	LIVINGSTON	47	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

80% FEDERAL
20% STATE

CODE NUMBER	ITEM	UNIT	TOTAL	ROADWAY X080-2A	STRUCTURE NO. 053-0075 X080-2A
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	720	720	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3580	3580	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3580	3580	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	26	26	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1617	1617	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	482	482	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	430	430	
• 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1790	1790	
• 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	240	240	
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	12	12	
78200405	GUARDRAIL MARKERS	EACH	16	16	
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	567	567	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	12	12	
• Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	72		72
Z0002600	BAR SPLICERS	EACH	131		131
Z0005215	BITUMINOUS STABILIZATION 6" AT STEEL PLATE BEAM GUARD RAIL	SQ YD	200	200	
Δ Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Δ Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
X3560130	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 9 INCH	SQ YD	832	832	
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIXTURE "C", N50	TON	265	265	
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	188	188	
X4080020	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE, N50	TON	3	3	

• SPECIALTY ITEM
Δ SAFETY PAY ITEM PAY CODE SFTY-3N

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
F.A.P. 681 (IL116) OVER FELKY SLOUGH
SECTION 113BR-2
LIVINGSTON COUNTY

DATE: 12/09/05
DRAWN BY: JJO
CHECKED BY: MSW