

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
681	113BR-2	LIVINGSTON	47	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

GUARDRAIL					
LOCATION	TRAFFIC BARRIER TERMINAL TY 1 SPECIAL (TANGENT)	SPBGR. TY A	TRAFFIC BARRIER TERMINAL TY 6A	GUARDRAIL MARKERS	TERMINAL MARKER-DIRECT APPLIED
	EACH	FOOT	EACH	EACH	EACH
	STA 433+73.12 RT TO STA 434+23.12 RT	1			1
STA 434+23.12 RT TO STA 435+85.62 RT		162.5		2	
STA 435+85.62 RT TO STA 436+18.77 RT			1	1	
STA 436+18.77 RT TO STA 437+30.58 RT				1	
STA 434+60.62 LT TO STA 435+10.62 LT	1			1	1
STA 435+10.62 LT TO STA 435+85.62 LT		75		1	
STA 435+85.62 LT TO STA 436+18.72 LT			1	1	
STA 436+18.72 LT TO STA 437+30.58 LT				1	
STA 437+30.58 RT TO STA 437+63.73 RT			1	1	
STA 437+63.73 RT TO STA 438+38.73 RT		75		1	
STA 438+38.73 RT TO STA 438+88.73 RT	1			1	1
STA 437+30.58 LT TO STA 437+63.73 LT			1	1	
STA 437+63.73 LT TO STA 439+26.23 LT		162.5		2	
STA 439+26.23 LT TO STA 439+76.23 LT	1			1	1
TOTAL	4	475	4	16	4

GUARDRAIL REMOVAL	
LOCATION	FOOT
STA 433+42 RT TO STA 436+18 RT	275
STA 434+42 LT TO STA 436+18 LT	176
STA 437+32 RT TO STA 439+09 RT	178
STA 437+32 LT TO STA 440+08 LT	276
TOTAL	905

ENGINEER'S FIELD OFFICE, TYPE A	
LOCATION	CAL MO
JOB SITE	4

MOBILIZATION	
LOCATION	L SUM
JOB SITE	1

TRAFFIC CONTROL - ALL STAGES		
ITEM	UNIT	TOTAL
TRAFFIC CONTROL AND PROTECTION, STD 701321	EACH	1
TRAFFIC CONTROL AND PROTECTION, STD 701306	L SUM	1
TRAFFIC CONTROL AND PROTECTION, STD 701326	L SUM	1
TRAFFIC CONTROL SURVEILLANCE	CAL DA	120
TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
TEMPORARY CONCRETE BARRIER	FOOT	482
RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	430
SHORT-TERM PAVEMENT MARKING	FOOT	720
WORK ZONE PAVEMENT MARKING REMOVAL	FOOT	1617
PAVEMENT MARKING REMOVAL	SQ FT	567
TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3580
TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3580
TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	26

PAINT PAVEMENT MARKING LINE		
LOCATION	4"	6"
	FOOT	FOOT
STA 432+20 RT TO STA 441+15 RT	895	
STA 432+20 LT TO STA 441+15 LT	895	
STA 432+20 C TO STA 441+15 C		240
TOTAL	1790	240

RAISED REFLECTIVE PAVEMENT MARKER		
LOCATION	REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER
	EACH	EACH
STA 432+20 TO STA 441+15	12	12
TOTAL	12	12

PAVEMENT MARKING REMOVAL	
LOCATION	SQ FT
STA 432+20 RT TO STA 435+85 RT	120
STA 432+20 LT TO STA 435+85 LT	120
STA 432+20 C TO STA 435+85 C	50
STA 437+65 RT TO STA 441+15 RT	116
STA 437+65 LT TO STA 441+15 LT	116
STA 437+65 C TO STA 441+15 C	45
TOTAL	567

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF QUANTITIES  
 F.A.P. 681 (IL116) OVER FELKY SLOUGH  
 SECTION 113BR-2  
 LIVINGSTON COUNTY

DATE: 12/09/05  
 DRAWN BY: JJO  
 CHECKED BY: MSW