

SUMMARY OF QUANTITIES

CONTRACT NO. 66566

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
68	105 BR-1	LIVINGSTON	45	3

STA.	TO STA.
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

PAY CODE NUMBER	PAY ITEM	UNIT	TOTAL	80% FED 20% STATE	
				ROADWAY X081-2A	BRIDGE X081-2A
20200500	EARTH EXCAVATION (WIDENING)	CU. YD.	49	49	
35600500	BITUMINOUS CONCRETE BASE COURSE WIDENING 10 INCHES	SQ. YD.	272	272	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	50	50	
40600300	AGGREGATE (PRIME COAT)	TON	0.2	0.2	
40600990	TEMPORARY RAMP	SQ. YD.	151	151	
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ. YD.	490	490	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	26	26	
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1
50102400	CONCRETE REMOVAL	CU. YD.	10.9		10.9
50300225	CONCRETE STRUCTURES	CU. YD.	7.8		7.8
50300260	BRIDGE DECK GROOVING	SQ. YD.	426		426
50300300	PROTECTIVE COAT	SQ. YD.	446		446
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ. FT.	4008		4008
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	9,490		9,490
50901005	STEEL BRIDGE RAIL, TYPE SM	FOOT	215		215
51500100	NAME PLATES	EACH	1		1
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4	
* 63304805	TRAFFIC BARRIER TERMINAL REMOVAL, TYPE 6	EACH	4	4	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL. MO.	2	2	
67100100	MOBILIZATION	L. SUM	1	1	
• 70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
• 70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L. SUM	1	1	
• 70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L. SUM	1	1	
• 70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L. SUM	1	1	
• 70103815	TRAFFIC CONTROL SURVEILLANCE	CAL. DAY	56	56	
• 70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70106700	TEMPORARY RUMBLE STRIP	EACH	6	6	
• 70300100	SHORT-TERM PAVEMENT MARKING	FOOT	150	150	
• 70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	4,860	4,860	
• 70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	210	210	

PAY CODE NUMBER	PAY ITEM	UNIT	TOTAL	80% FED 20% STATE	
				ROADWAY X081-2A	BRIDGE X081-2A
• 70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	52	52	
70301000	WORKZONE PAVEMENT MARKING REMOVAL	SQ. FT.	1,184	1,184	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	450	450	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	450	450	
• 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1,620	1,620	
• 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	210	210	
• 78100100	RAISED REFLECTIVE PAVEMENT MARKERS	EACH	7	7	
• 78100105	RAISED REFLECTIVE PAVEMENT MARKERS (BRIDGE)	EACH	1	1	
• 78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8	
• 78300100	PAVEMENT MARKING REMOVAL	SQ. FT.	610	610	
• 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	8	8	
X0323557	BRIDGE JOINT SYSTEM (EXPANSION), 1"	FOOT	92		92
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	42	42	
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	22	22	
X5030305	CONCRETE WEARING SURFACE, 5"	SQ. YD.	446		446
* Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	48		48
Z0002600	BAR SPLICERS	EACH	106		106
** Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
** Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
66410400	CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED	FOOT	109	109	

- * SPECIALTY ITEM
- ** S-TY-3N

PLOT DATE = 12/20/05
 FILE NAME = J:\03236\03236.W011.SUM.dgn
 PLOT SCALE = 0.25000000 / IN.
 REFERENCE = REF.
 OPERATOR = mchellal

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

FAP ROUTE 68 (IL RTE. 23)
SECTION 105 BR-1
LIVINGSTON COUNTY

VERT. SCALE: HORIZ. DRAWN BY: BISHOP
DATE: CHECKED BY: BOTT

GREEN & BRADFORD, INC.
OF SPRINGFIELD
CONSULTING ENGINEERS
INCORPORATED
1111 SOUTH WASHINGTON STREET
SPRINGFIELD, ILLINOIS 62760
PHONE: 217-223-1100
FAX: 217-223-1101
WWW.GREENANDBRADFORD.COM

COMPUTER FILE NO.
03236.W011.SUM

PROJECT 03236 W011
12/20/05 - MML