

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
693	22 BR	MC LEAN	28	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

				80% FED 20% STATE		
				ROADWAY	SN 057-0076	SFTY-3N
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QNTY	X08D-2A	X080-2A	
20200100	EARTH EXCAVATION	CU YD	85	85	0	
20400800	FURNISHED EXCAVATION	CU YD	49	49	0	
25000200	SEEDING, CLASS 2	ACRE	0.25	0.25	0	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	9.9	9.9	0	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	9.9	9.9	0	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	9.9	9.9	0	
25100115	MULCH, METHOD 2	ACRE	0.25	0.25	0	
25100630	EROSION CONTROL BLANKET	SQ YD	532	532	0	
28000300	TEMPORARY DITCH CHECKS	EACH	4	4	0	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	11	11	0	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	111	111	0	
40600300	AGGREGATE (PRIME COAT)	TON	3	3	0	
40600990	TEMPORARY RAMP	SQ YD	43	43	0	
44000075	BITUMINOUS SURFACE REMOVAL (COLD MILLING)	SQ YD	1383	1383	0	
48200700	BITUMINOUS SHOULDERS 9"	SQ YD	536	536	0	
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	0	1	
50102400	CONCRETE REMOVAL	CU YD	2.5	0	2.5	
50300225	CONCRETE STRUCTURES	CU YD	4.7	0	4.7	
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	1216	0	1216	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	3340	0	3340	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	360	0	360	
△ 50901005	STEEL BRIDGE RAIL, TYPE SM	FOOT	145	0	145	
51500100	NAME PLATES	EACH	1	0	1	
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	148	0	148	
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	368	0	368	
△ 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	400	400	0	
△ 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4	0	
△ 63100169	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	EACH	4	4	0	
63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	360	360	0	
△ 63300205	REMOVAL AND REINSTALLATION OF EXISTING STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	80	80	0	
△ 63300410	REMOVAL AND REINSTALLATION OF EXISTING TRAFFIC BARRIER TERMINAL, TYPE 1A	EACH	2	2	0	
△ 63300445	REMOVAL AND REINSTALLATION OF EXISTING TRAFFIC BARRIER TERMINAL, TYPE 5A	EACH	2	2	0	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	GAL MO	3	3	0	
67100100	MOBILIZATION	L SUM	1	1	0	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	0	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	0	

△ SPECIALTY ITEMS

PLOT DATE = 12/15/2005  
 FILE NAME = \\s8\summary\of\quantities.dgn  
 PLOT SCALE = 80.0000 / IN.  
 USER NAME = CFC

**COOMBE-BLOXDORF P.C.**  
 Engineers / Land Surveyors  
 Springfield, Illinois  
 Design Firm License No. 184-002703

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
  
 SUMMARY OF QUANTITIES  
 IL ROUTE 9 OVER MONEY CREEK  
 FAP RT 693, SECTION 22 BR  
 MC LEAN COUNTY  
  
 SCALE: \_\_\_\_\_  
 DATE \_\_\_\_\_  
 DRAWN BY CFC / TFG  
 CHECKED BY MCB