

F.A.U. RTE.	SECTION	COUNTIES	TOTAL SHEETS	SHEET NO.
6088	17N	*	18	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

* LASALLE & BUREAU

FURNISHED EXCAVATION AND SEEDING SCHEDULE							
LOCATION	FURN EXC	EARTH EXC WIDENING	SEEDING CL 2	EROSION CONTROL BLANKET	NIT FERT NUT	PHOS FERT NUT	POT FERT NUT
	CU YD	CU YD	ACRE	SQ YD	LB	LB	LB
PVMT REM AREA	79		0.1	484	9	9	9
DALZELL RD WIDENING		50					
TOTAL	79	50	0.1	484	9	9	9

MAINLINE SCHEDULE												
LOCATION	BIT SURF REM	BIT CONC SURF CSE SUPERPAVE	BIT CONC BSE CSE WIDENING	SUBBASE GRAN MAT	AGG SHLD TY B	TEMP RAMP	BIT MAT (PR CT)	AGG (PR CT)	MIX FOR CRACKS, JTS & FLGWYS	LEVEL BINDER (H.M.)	ISLAND REM	PVMT REM
	1 1/2" SQ YD	TON	10 3/4" SQ YD	TY A, 4" SQ YD	TON	SQ YD	GAL	TON	TON	TON	SQ FT	SQ YD
DALZELL ROAD	2340	197	172	184	11	136	187	5	1	1	474	238
TOTAL	2340	197	172	184	11	136	187	5	1	1	474	238

NOTE: AGGREGATE SHOULDER QUANTITY SHOULD ONLY BE USED IF DEEMED NECESSARY AND DIRECTED BY THE ENGINEER

THERMOPLASTIC PAVEMENT MARKING SCHEDULE									
LOCATION	THERMO PAVEMENT MARKING REMOVAL	THERMOPLASTIC PVMT MARKING		THERMO PVMT MARK	THERMO PVMT MARK	THERMO PVMT MARK	THERMO PVMT MARK	RAISED REF PVMT MARKER REMOVAL	RAISED REFLECT PVMT MARKER
		WHITE 4"	YELLOW 4"	WHITE 8"	YELLOW 12"	WHITE 24"			
		SQ FT	FOOT	FOOT	FOOT	FOOT	SQ FT		
DALZELL ROAD		800	728	342	97	58	83.2	22	22
US 6 - EAST LEG	1507	930	1760	595	107	24	140.4	35	35
US 6 - WEST LEG	1249	970	1840	318	107	24	46.8	30	30
SUB TOTAL	2756	2700	4328	1255	311	106	270	87	87
TOTAL			7028	1255	311	106	270.4	87	87

TEMPORARY PAVEMENT MARKING SCHEDULE						
LOCATION	TEMPORARY PVMT MARKING		TEMPORARY PVMT MARK	TEMPORARY PVMT MARK	TEMPORARY PVMT MARK	TEMPORARY PVMT MARK
	WHITE 4"	YELLOW 4"	WHITE 8"	YELLOW 12"	WHITE 24"	LETTERS & SYMBOLS
	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT
DALZELL ROAD	800	728	342	97	58	83.2
SUB TOTAL	800	728	342	97	58	83
TOTAL	1528		342	97	58	83

SHORT-TERM PAVEMENT MARKING SCHEDULE			
LOCATION	SHORT-TERM PAVEMENT MARKING		WORK ZONE PAV'T MARKING REMOVAL
	WHITE	YELLOW	SQ FT
	FOOT	FOOT	
DALZELL ROAD	569	73	107
SUB TOTAL	569	73	107
TOTAL	642		107

12/13/2005
c:\p\projects\ep01205\summary.dgn