

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(50-5,6)I	LASALLE	9	5
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

MAINLINE SCHEDULE								
LOCATION STA TO STA		BIT SURF REM 3 1/2"	POLY BIT CONC SURF CSE SUPERPAVE	BIT CONC BINDER CSE SUPERPAVE	BIT MATL PR CT	AGG PR CT	MIX FOR CR JTS & FLNGWYS	LEVEL BIND (HM)
	LENGTH	SQ YD	TON	TON	GAL	TON	TON	TON
LASALLE CO.								
EASTBOUND DRIVING LANE								
672+50 TO 688+37.54	1587.54	2117	148	267	339	8.5	0.6	1.1
688+37.54 (BK) = 688+37.06 (AH)								
688+37.06 TO 728+00	3962.94	5284	370	666	845	21.1	1.6	2.6
737+00 TO 768+00	3100	4133	289	521	661	16.5	1.2	2.1
873+00 TO 874+00	100	133	9	17	21	0.5	0	0.1
982+00 TO 983+50	150	200	14	25	32	0.8	0.1	0.1
1000+00 TO 1092+50	9250	12333	863	1554	1973	49.3	3.7	6.2
1150+00 TO 1151+00	100	133	9	17	21	0.5	0	0.1
WESTBOUND DRIVING LANE								
776+50 TO 777+00	50	67	5	8	11	0.3	0	0
780+00 TO 782+50	250	333	23	42	53	1.3	0.1	0.2
884+00 TO 887+50	350	467	33	59	75	1.9	0.1	0.2
936+00 TO 937+00	100	133	9	17	21	0.5	0	0.1
989+00 TO 993+50	450	600	42	76	96	2.4	0.2	0.3
1001+00 TO 1002+50	150	200	14	25	32	0.8	0.1	0.1
1073+50 TO 1074+00	50	67	5	8	11	0.3	0	0
1086+00 TO 1086+50	50	67	5	8	11	0.3	0	0
1089+00 TO 1091+00	200	267	19	34	43	1.1	0.1	0.1
TOTAL	19900.48	26534	1857	3344	4245	106.1	7.8	13.3

PAVEMENT MARKING SCHEDULE				
LOCATION STA TO STA		THERMOPLASTIC PAVEMENT MARKING, 4"	SHORT TERM PAVEMENT MARKING	WORK ZONE PVMT MARK REMOVAL
	LENGTH	FOOT	FOOT	SQ FT
LASALLE CO.				
EASTBOUND DRIVING LANE				
672+50 TO 688+37.54	1587.54	1587.54	64	21.3
688+37.54 (BK) = 688+37.06 (AH)				
688+37.06 TO 728+00	3962.94	3962.94	160	53.3
737+00 TO 768+00	3100	3100	124	41.3
873+00 TO 874+00	100	100	4	1.3
982+00 TO 983+50	150	150	8	2.7
1000+00 TO 1092+50	9250	9250	372	124
1150+00 TO 1151+00	100	100	4	1.3
WESTBOUND DRIVING LANE				
776+50 TO 777+00	50	50	4	1.3
780+00 TO 782+50	250	250	12	4
884+00 TO 887+50	350	350	16	5.3
936+00 TO 937+00	100	100	4	1.3
989+00 TO 993+50	450	450	20	6.7
1001+00 TO 1002+50	150	150	8	2.7
1073+50 TO 1074+00	50	50	4	1.3
1086+00 TO 1086+50	50	50	4	1.3
1089+00 TO 1091+00	200	200	8	2.7
TOTAL	19900.48	19900.48	816	271.8

12/13/2005
c:\p\proj\fact\ve01806.dwg\p1.s.dgn