

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
840	136 BR-1	IROQUOIS	45	3
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

PAY CODE NUMBER	DESCRIPTION	UNIT	TOTAL	80% FED 20% STATE	
				ROADWAY X081-2A	BRIDGE X081-2A
20200500	EARTH EXCAVATION (WIDENING)	CU YD	34	34	
28100107	STONE RIPRAP, CLASS A4	SQ YD	226	226	
28200400	FILTER FABRIC	SQ YD	226	226	
35600500	BITUMINOUS CONCRETE BASE COURSE WIDENING 10 INCHES	SQ YD	122	122	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	60	60	
40600300	AGGREGATE (PRIME COAT)	TON	1.2	1.2	
40600990	TEMPORARY RAMP	SQ YD	113	113	
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	598	598	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	7	7	
50101500	REMOVAL OF EXISTING SUPERSTRUCTURE	EACH	1		1
50102400	CONCRETE REMOVAL	CU YD	1.9		1.9
50300120	PREFORMED JOINT SEAL 2 1/2"	FOOT	33		33
50300225	CONCRETE STRUCTURES	CU YD	1.9		1.9
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	1729		1729
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	2680		2680
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	470		470
50901005	STEEL BRIDGE RAIL, TYPE SM	FOOT	187		187
51500100	NAME PLATES	EACH	1		1
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	192		192
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	523		523
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	118	118	
63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4	
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	3	3	
63200310	GUARDRAIL REMOVAL	FOOT	390	390	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	2	
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DAY	42	42	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70106700	TEMPORARY RUMBLE STRIPS	EACH	6	6	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	210	210	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	4236	4236	

PAY CODE NUMBER	DESCRIPTION	UNIT	TOTAL	80% FED 20% STATE	
				ROADWAY X081-2A	BRIDGE X081-2A
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	180	180	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	48	48	
70301000	WORKZONE PAVEMENT MARKING REMOVAL	SQ FT	1473	1473	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	350	350	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	350	350	
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1412	1412	
78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	180	180	
78100100	RAISED REFLECTIVE PAVEMENT MARKERS	EACH	4	4	
78200410	GUARDRAIL MARKERS, TYPE A	EACH	7	7	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	532	532	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	4	4	
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	83	50	33
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	TON	26	26	
X7200201	WIDTH RESTRICTION SIGNING	LSUM	1	1	
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	22	22	
Z0002600	BAR SPLICERS	EACH	9	9	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	

*SPECIALTY ITEM
△ SFTY-3N

PLOT DATE = 12/21/2005
FILE NAME = J:\A\2325\W012\URAW\INDS\SUMW012.dgn
PLOT SCALE = 50.0000 / IN.
REFERENCE = .REF.
OPERATOR = michel1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 FAS 840 (IL RTE 49)
 OVER SHAVETAIL CREEK
 SEC. 136 BR-1
 IROQUOIS COUNTY

SCALE: VERT. DATE 10/21/05
 HORIZ. DATE 10/21/05

DRAWN BY SUTHEARD
 CHECKED BY BOTI

COMPUTER FILE NO. SUMW012
 PROJECT 03236 W012
 12/6/05-MML

GREENE & BRADFORD, INC.
 OF SPRINGFIELD
 REGISTERED PROFESSIONAL ENGINEERS
 PROFESSIONAL DESIGN FIRM NO. 044-001077
 CIVIL ENGINEERS AND ARCHITECTS
 1211 S. BRADLEY ST., SPRINGFIELD, IL 62760
 TEL: 217-223-1222 FAX: 217-223-1223

SUMMARY OF QUANTITIES