

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6659	*	PEORIA	40	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

-04 BOX CULVERT EXT 2006

TREE REMOVAL (6 TO 15 UNITS DIA)	
LOCATION	UNITS
RIGHT SIDE	11
RIGHT SIDE	15
RIGHT SIDE	15
RIGHT SIDE	13
RIGHT SIDE	14
RIGHT SIDE	11
RIGHT SIDE	15
TOTAL	94

TREE REMOVAL (OVER 15 UNITS DIA)	
LOCATION	UNITS
RIGHT SIDE	18
RIGHT SIDE	18
RIGHT SIDE	18
LEFT SIDE	16
LEFT SIDE	43
LEFT SIDE	18
TOTAL	131

PERIMETER EROSION BARRIER	
LOCATION	FOOT
RT. STA. 381+45	48
LT. STA. 381+03	48
TOTAL	96

BITUMINOUS SHOULDERS SUPERPAVE		
LOCATION	SQ FT	TON
RT. STA. 378+93.28 - 381+55.46	1048.7	52.2
RT. STA. 381+55.46 - 381+91.20	122.7	6.1
LT. STA. 379+00 - 382+67.13	1468.5	73.1
TOTAL		131.4

APPLICATION RATE OF 112 LB/SQ YD/INCH

LOCATION	EARTH EXCAVATION	FURNISHED EXCAVATION	TOPSOIL FURNISH & PLACE 4"	SEEDING, CLASS 3	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	TEMPORARY SEEDING	EROSION CONTROL BLANKET
	CU YD	CU YD	SQ YD	ACRE	POUND	POUND	POUND	ACRE	SQ YD
RIGHT SIDE	23.2	533.5	486.1	0.14	12.6	12.6	12.6	0.14	486.1
LEFT SIDE	35	490.3	555.1	0.15	13.5	13.5	13.5	0.15	555.1
TOTAL	58.2	1023.8	1041.2	0.29	26.1	26.1	26.1	0.29	1041.2

LOCATION	STONE DUMPED RIPRAP, CLASS A4	FILTER FABRIC
	TON	SQ YD
RT STA 381+39.3 to 381+54.3	8.9	13.3
LT STA 381+02 to 381+17	8.9	13.3
TOTAL	17.8	26.6

AGGREGATE SHOULDERS TYPE B	
LOCATION	FOOT
RT STA 378+94 to 379+51	9.6
RT STA 382+12 to 381+38.5	6.8
LT STA 378+58 to 379+42	6.5
LT STA 382+77 to 382+17	8.4
TOTAL	31.3

	CONCRETE REMOVAL	CONCRETE HEADWALL REMOVAL	REINFORCEMENT BARS	BOX CULVERT END SECTIONS	PRECAST CONCRETE BOX CUVLERT 4'X3'	CLASS SI CONCRETE
LOCATION	CU YD	EACH	POUND	EACH	FOOT	CU YD
RT. STA. 381+27.34	1.3	1	29	1	18	0.41
LT. STA. 381+27.34	1.3	1	29	1	12	0.41
TOTAL	2.6	2	58	2	30	0.82

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULES OF QUANTITIES
 SCALE: VERT. _____
 DATE _____ HORIZ. _____
 DRAWN BY _____
 CHECKED BY _____

PLOT DATE = 12/15/2005
 FILE NAME = I:\Projects\68325\Drawings\Quantities.dwg
 PLOT SCALE = 1/8"=1'-0"
 REFERENCE = #REF#