

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
646		PEORIA	30	2

D4 SLOPE REPAIR 2006

# COMMITMENTS

The Contractor shall notified GRACE PRESBYTERIAN CHURCH (Gregory J. Tiemeier, Business Administrator, Tel. 309-688-3641, ext. 217) prior to the beggining of the construction to coordinate the removal of the retaining wall.

# GENERAL NOTES

## ENVIRONMENTAL REVIEWS

Prior to the use of any proposed borrow areas, use areas (temporary access roads, detours, run-arounds, etc.) and/or waste areas, the Contractor shall file the required environmental resource request surveys according to Section 107.22 of the Standard Specifications. These surveys are required in order for the Department to conduct cultural and biological resource surveys for the proposed site.

Prior to any waste materials being removed from the construction site the required environmental resource surveys will need to be obtained and filed by the Contractor. Excess waste products removed from the construction site shall be disposed of as required in Section 202.03 of the Standard Specifications.

Any protruding metal bars shall be removed prior to the disposal of broken concrete at approved disposal sites.

The required environmental resource documentation shall include the following:

- \* BDE Form 2289 (Environmental Survey Request)
- \* A location map showing the size limits and location of the use area
- \* Signed property owner agreement form
- \* Color photographs depicting the use area

Please note that a minimum of two weeks shall be allowed for the District to obtain the required environmental clearances.

## UTILITIES - LOCATIONS / INFORMATION ON PLANS

The locations of existing water mains, gas mains, sewers, electric power lines, telephone lines and other utilities as shown on the plans are based on careful field investigation and the best information available, but they are not guaranteed. Unless elevations are shown --- all utility locations shown on the cross sections are based on the approximate depth supplied by the utility company. It shall be the Contractor's responsibility to ascertain their exact location from the utility companies and by field inspection.

## PLAN ELEVATIONS - U. S. G. S. MEAN SEA LEVEL DATUM

All elevations shown on the plans are established from U. S. G. S. mean sea level datum.

# JOB SPECIFIC NOTES

## RETAINING WALL

Retaining wall removal and replacement including pipe underdrains and pipe underdrains special will be constructed by GRACE PRESBYTERIAN CHURCH.

## PARKING LOT REPAIR

The following pay items will be used only if the parking area inside the Temporary Easement is damaged during the slope repair.

- \* Bituminous Material (Prime Coat)
- \* Aggregate (Prime Coat)
- \* Bituminous Surface Removal 2"
- \* Bituminous Concrete Surface Course, Superpave, Mix C, N50 (Non QC/QA)
- \* Paint Pavement Marking - Line 4"

## BITUMINOUS CONCRETE MIXTURE REQUIREMENTS

The following mixture requirements are applicable to this project:

Mixture Uses	Bit. Conc. Surf. Crs. , Superpave, Mix C, N50 (Non QC/QA)
AC/PG:	PG 64-22
Rap% (Max):*	155%
Design Air Voids:	4.25% @ N=50
Mixture Composition: (Gradation Mixture)	IL 9.5 or 12.5
Friction Aggregate:	MIX C

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**COMMITMENTS  
AND  
GENERAL NOTES**