

SCHEDULE OF QUANTITIES

CODE NO.	25000400	25000500	25000600	25200200	21101615	25200100	25002300
PAY ITEMS	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	SUPPLEMENTAL WATERING	TOPSOIL FURNISH & PLACE, 4"	SODDING	TEMPORARY SEEDING
LOCATION	POUND	POUND	POUND	UNIT	SQ YD	SQ YD	ACRE
STA 266+37.50 TO 267+08.25	2	2	2	4.8	96	96	0.02
TOTAL	2	2	2	4.8	96	96	0.02

50800105	
REINFORCEMENT BARS	
LOCATION	POUND
STA. 266+36.23 TO STA. 266+45.60	200
TOTAL	
200	

20200100	
EARTH EXCAVATION	
LOCATION	CU YD
STA 266+36.23 TO 267+40	58
TOTAL	
58	

28400100	
GABIONS	
LOCATION	CU YD
STA. 267+40 - 267+43	5
TOTAL	
5	

50800205	
REINFORCEMENT BARS, EPOXY COATED	
LOCATION	POUND
STA. 266+36.23 TO STA. 266+45.60	82
TOTAL	
82	

28100107	
STONE RIPRAP, CLASS A4	
LOCATION	SQ YD
STA 266+36.23 TO STA 267+40	166
TOTAL	
166	

50102400	
CONCRETE REMOVAL	
LOCATION	CU YD
STA 266+36.23 TO STA 266+39.67	0.13
TOTAL	
0.13	

51100300	
SLOPE WALL, 6 INCH	
LOCATION	SQ YD
STA 266+37 TO STA. 267+02 (WEST WALL)	93
STA 266+59 TO STA. 267+01 (EAST WALL)	50
STA 266+37 TO STA. 266+53 (EAST WEDGE)	13
TOTAL	
156	

28200200	
FILTER FABRIC	
LOCATION	SQ YD
STA 266+36.23 TO 267+43	171
TOTAL	
171	

50104650	
SLOPE WALL REMOVAL	
LOCATION	SQ YD
STA 266+37 TO STA. 267+02 (WEST WALL)	74
STA 266+59 TO STA. 267+01 (EAST WALL)	50
STA 266+37 TO STA. 266+53 (EAST WEDGE)	13
TOTAL	
137	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES