

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
817	106BR-1	WASHINGTON	23	2
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 76863				

INDEX OF SHEETS

1. COVER PAGE
2. INDEX OF SHEETS/HIGHWAY STANDARDS/GENERAL NOTES
3. SUMMARY OF QUANTITIES
4. TYPICAL SECTIONS/MIXTURE REQUIREMENTS/MILLING DETAIL
5. SCHEDULES & DETECTOR LOOP IN TRENCH DETAIL
6. WIDE LOAD SIGNING
- 7 - 8. STAGING PLAN
9. PLAN AND PROFILE SHEETS
- 10 - 23. BRIDGE PLANS

HIGHWAY STANDARDS

000001-04	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001001	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH OF A FOOT
515001-02	NAME PLATE FOR BRIDGES
630001-05	STEEL PLATE BEAM GUARDRAIL
630301-03	SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARDRAIL TERMINALS
631032-01	TRAFFIC BARRIER TERMINAL, TYPE 6A
635006-02	REFLECTOR AND TERMINAL MARKER PLACEMENT
635011-01	REFLECTOR MARKER AND MOUNTING DETAILS
701006-02	OFF-ROAD OPERATIONS, 2L, 2W, 4.5m (15') TO 600m (24') FROM PAVEMENT EDGE
701011-01	OFF-ROAD MOVING OPERATIONS, 2L, 2W, DAY ONLY
701201-02	LANE CLOSURE, 2L, 2W, DAY ONLY, FOR SPEEDS >= 45 MPH
701306-01	LANE CLOSURE, 2L, 2W, SLOW MOVING OPERATIONS DAY ONLY, FOR SPEEDS >= 45 MPH
701311-02	LANE CLOSURE, 2L, 2W, MOVING OPERATIONS - DAY ONLY
701321-08	LANE CLOSURE, 2L, 2W, BRIDGE REPAIR WITH BARRIER
702001-05	TRAFFIC CONTROL DEVICES
704001-02	TEMPORARY CONCRETE BARRIER
780001-01	TYPICAL PAVEMENT MARKINGS
781001-02	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS

GENERAL NOTES

1. THE STANDARDS AND REVISION NUMBERS SHALL APPLY TO THIS PROJECT.
2. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.
3. THE THICKNESS OF THE BITUMINOUS MIXTURES SHOWN ON THE PLANS IS THE NOMINAL THICKNESS. DEVIATIONS MAY OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE BITUMINOUS MIXTURE IS PLACED.
4. SAW CUTTING ON ALL EDGES FOR REMOVAL ITEMS SHALL BE INCLUDED IN THE COST OF THE REMOVAL ITEM AS INDICATED AND ACCORDING TO SECTION 440 OF THE STANDARD SPECIFICATIONS. SAW CUTTING FOR ALL REMOVAL ITEMS SHALL BE FULL-DEPTH IN ORDER TO AVOID DAMAGE TO THOSE ITEMS REMAINING IN PLACE.
5. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO UTILITIES WITHIN THE PROJECT AREA BEFORE DIGGING BY CALLING J.U.L.I.E. AND BY NOTIFYING NON-J.U.L.I.E. MEMBERS INDIVIDUALLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
 - EGYPTIAN TELEPHONE CO-OP. ASSN.
 - TRI-COUNTY ELECTRIC COOPERATIVE, INC.
 MEMBERS OF J.U.L.I.E. (800) 892-0123 ARE INDICATED BY *. NON-MEMBERS MUST BE NOTIFIED INDIVIDUALLY.
6. IF ANY SECTION OR SUB-SECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED OR RESURFACED OVER. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL PROPERTY MARKERS AND MONUMENTS UNTIL THE OWNER, AN AUTHORIZED SURVEYOR, OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION.
7. A SURVEY MONUMENT IS LOCATED ON THE SOUTHWEST TOP WINGWALL OF THE STRUCTURE.
8. THE CONTRACTOR SHALL NOT ALLOW ANY DEBRIS TO FALL INTO ELKHORN CREEK.
9. ALL EXISTING CONCRETE IN THE CREEK, UNDER THE BRIDGE, MUST BE REMOVED. THIS WORK WILL NOT BE MEASURED FOR PAYMENT, BUT SHALL BE INCLUDED IN THE COST OF STONE RIPRAP.
10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR SEEDING, FERTILIZING, AND MULCHING ANY AREAS DISTURBED BY THE CONTRACTOR. THIS WORK WILL NOT BE MEASURED FOR PAYMENT, BUT SHALL BE INCLUDED IN THE COST OF THE CONTRACT. THE SEEDING SHALL BE CLASS 2. THE APPLICATION OF THE SEEDING, FERTILIZER, AND MULCH SHALL BE TO THE SATISFACTION OF THE ENGINEER. FINAL SEEDING SHALL BE PERFORMED AS SOON AS POSSIBLE.
11. AN ESTIMATED QUANTITY OF 100 CU YD OF FURNISHED EXCAVATION HAS BEEN ADDED TO THE CONTRACT FOR ADDITIONAL EARTH BEHIND THE GUARDRAIL.
12. A QUANTITY OF 900 FEET OF TEMPORARY PAVEMENT MARKING - LINE 6" HAS BEEN ADDED IN THE PLANS FOR PAINTING THE BOTTOM 6" OF THE TEMPORARY CONCRETE BARRIER.
13. THE CONTRACTOR HAS THE OPTION OF DISPOSING OF THE BITUMINOUS MILLINGS AND CRUSHED CONCRETE AT MR. BINSBACHER'S FARM LOCATED LESS THAN ONE MILE FROM THE JOB SITE. THE CONTRACTOR CAN CONTACT EITHER MR. VALROY BINSBACHER AT (618) 566-4300 OR MR. RAMZY BINSBACHER AT (618) 980-1634.

COMMITMENTS

NONE

PLOT DATE = 12/16/2008
 FILE NAME = c:\p\106br1\106br1.dgn
 PLOT SCALE = 50.0000 / 1 IN.
 REFERENCE = *REF*

REVISIONS		SCALE: VERT. / HORIZ.	DRAWN BY / CHECKED BY
NAME	DATE		

ILLINOIS DEPARTMENT OF TRANSPORTATION
INDEX OF SHEETS/GENERAL NOTES/HIGHWAY STANDARDS
 FAP ROUTE 817
 SECTION 106BR-1
 WASHINGTON COUNTY