

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	05-00180-00-BR	COOK	14	4
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 83822				

ITEM NO.	CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE
					CULVERT X628-2A
• 43	72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	1	1
• 44	72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	28	28
• 45	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	50	50
• 46	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	84	84
47	78300100	PAVEMENT MARKING REMOVAL	SQ FT	17	17
• 48	80700140	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	2	2
• 49	81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	147	147
• 50	81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	147	147
51	X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	1	1
52	X0632001	CLEAR PROTECTIVE COATING FOR CONCRETE	SQ FT	2,380	2,380
53	XX001978	RAILROAD FLAGMEN	L SUM	1	1
54	X6640200	TEMPORARY CHAIN LINK FENCE	FOOT	50	50
55	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1
56	54003000	CONCRETE BOX CULVERTS	CU YD	155	155
57	XX005817	FORMLINER LIMESTONE SURFACE	SQ FT	500	500
• 58	XX006495	LIGHT POLE FOUNDATION, 18" DIAMETER	FOOT	8	8
59	50900805	PEDESTRIAN RAILING	FOOT	104	104
61	XX006496	PORTLAND CEMENT CONCRETE SIDEWALK AND CURB WALL	CU YD	75	75
62	X0324160	CATCH BASIN WITH HALF TRAP, 4' DIAMETER (INCLUDING FRAME AND LTD)	EACH	1	1
63	X0322033	STORM SEWER (WATER MAIN REQUIREMENTS) 12"	FOOT	40	40
64	42400800	DETECTABLE WARNINGS	SQ FT	24	24
66	XX005195	COMBINED SEWER MANHOLE, 4'-DIAMETER TYPE 1 FRAME, CLOSED LTD	EACH	1	1

• INDICATES SPECIALTY ITEM

ILLINOIS DEPARTMENT OF TRANSPORTATION
 PEDESTRIAN CULVERT UNDER UNION PACIFIC RAILROAD

SUMMARY OF QUANTITIES

NO SCALE
 DATE 01/20/06

DRAWN BY JMH
 CHECKED BY SOC