

**GENERAL NOTES**

1. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL SECTION OR SUBSECTION MONUMENTS OR PROPERTY OR REFERENCE MARKERS UNTIL THE OWNER, HIS AGENT OR AN AUTHORIZED SURVEYOR HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATIONS.
2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONTACTING THE OWNERS OF ALL EXISTING UTILITIES SO THAT THE UTILITIES AND THEIR APPURTENANCES MAY BE LOCATED AND ADJUSTED OR MOVED, IF NECESSARY, PRIOR TO THE START OF CONSTRUCTION OPERATIONS. THE CONTRACTOR SHALL COOPERATE WITH ALL UTILITY OWNERS AS PROVIDED IN THE STANDARD SPECIFICATIONS. UTILITY LOCATIONS ARE APPROXIMATE. THE CONTRACTOR SHALL USE CAUTION WHERE THERE ARE POTENTIAL CONFLICTS. PRIOR TO THE CONSTRUCTION OF THE SIGHT SCREEN (WOODEN FENCE), THE CONTRACTOR SHALL NOTIFY THE VILLAGE TO LOCATED EXISTING WATER MAIN, WATER SERVICES, SANITARY SEWER, AND SANITARY SEWER SERVICES WHERE THE PROPOSED SIGHT SCREEN (WOODEN FENCE) WILL CROSS.
3. ALL AGGREGATE USED ON THIS PROJECT SHALL BE CRUSHED MATERIAL.
4. ALL SAW CUTTING SHALL BE INCLUDED IN THE COST OF THE ITEM BEING REMOVED.
5. ALL CONSTRUCTION PERSONNEL WILL BE REQUIRED TO WEAR FLUORESCENT ORANGE VEST AT ALL TIMES WHILE ON THE CONSTRUCTION SITE. FLAGGERS ARE REQUIRED TO WEAR GREEN VESTS AS DESCRIBED IN THE SPECIAL PROVISIONS. COMPLIANCE WITH THIS REQUIREMENT SHALL BE INCLUDED IN THE PAY ITEM FOR TRAFFIC CONTROL AND PROTECTION, STANDARD 701101 AND 701106.
6. DURING CONSTRUCTION STAGING OPERATIONS, THE CITY OF COUNTRY CLUB HILLS POLICE AND FIRE PROTECTION DISTRICTS SHALL BE NOTIFIED IN WRITING 48 HOURS PRIOR TO STREET CLOSURES. EMERGENCY ACCESS SHALL BE ALLOWED AT ALL TIMES.
7. BARRICADES: THE CONTRACTOR SHALL PROVIDE AND INSTALL TWO (2) WEIGHTED SAND BAGS ON EACH TYPE I OR TYPE II BARRICADE USED-ONE (1) WEIGHTED SAND BAG ACROSS EACH BOTTOM RAIL.
8. CONTRACTOR SHALL PROVIDE DRIVEWAY ACCESS TO PROPERTIES AT ALL TIMES. WHEN CONSTRUCTION IMPACTS A DRIVEWAY, IMPACTED PROPERTY OWNERS SHALL BE NOTIFIED 48 HOURS PRIOR.
9. BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS FACILITIES. (48 HOUR NOTIFICATION IS REQUIRED)
10. THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND THE CITY OF COUNTRY CLUB HILLS.
11. MAILBOX RELOCATION SHALL BE INCLUDED IN THE COST OF SIGHT SCREEN (WOODEN FENCE).
12. THE EXISTING SIDEWALK SHALL BE PROTECTED DURING CONSTRUCTION. ALL EXISTING SIDEWALK DAMAGED DURING CONSTRUCTION REQUIRES REMOVAL AND REPLACEMENT. THIS WORK SHALL BE INCLUDED IN THE COST OF SIGHT SCREEN (WOODEN FENCE).
13. WHERE POSSIBLE, EXISTING UTILITY POLES SHALL BE CENTERED BETWEEN PROPOSED FENCE POSTS TO ALLOW FOR FUTURE ACCESS. THE CONTRACTOR SHALL MARK THE LOCATIONS OF EACH POST AND RECEIVE APPROVAL FROM THE ENGINEER PRIOR TO THE COMMENCEMENT OF POST HOLE EXCAVATION.

**HIGHWAY STANDARDS**

STANDARD NO.	DESCRIPTION
000001-04	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
280001-02	TEMPORARY EROSION CONTROL SYSTEMS
701101-01	OFF-ROAD OPERATIONS, MULTILANE, 4.5m (15') TO 600mm (24") FROM PAVEMENT EDGE
701106-01	OFF-ROAD OPERATIONS, MULTILANE, MORE THAN 45m (15') AWAY
701606-04	URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN
701801-03	LANE CLOSURE, MULTILANE, 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
702001-05	TRAFFIC CONTROL DEVICES

**INDEX OF SHEETS**

SHEET NO.	TITLE
1.	COVER SHEET
2.	STATE STANDARDS, INDEX OF SHEETS, BENCHMARKS, SUMMARY OF QUANTITIES AND GENERAL NOTES
3.	TYPICAL SECTIONS AND MISCELLANEOUS DETAILS
4.-5.	PLAN SHEETS: CRAWFORD AVENUE & 167TH STREET
6.	TC-10 DISTRICT 1 TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS AND DRIVEWAYS

**BENCHMARKS**

TBM #4	RR SPIKE SET IN NORTH FACE OF POWER POLE 1ST POLE WEST OF BRIARGATE AND 167TH STREET ELEV. = 668.97
CP #6	CUT CROSS SET IN SIDEWALK 9' SOUTH OF WALK END S.E CORNER OF CRAWORD AVE. & 167TH STREET ELEV. = 659.93

**SUMMARY OF QUANTITIES**

F.A.U. ROUTE 3778 / CRAWFORD AVENUE  
F.A.U. ROUTE 1609 / 167TH STREET

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE
* 20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	60.98	60.98
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1,110	1,110
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	34.4	34.4
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	34.4	34.4
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	34.4	34.4
25200100	SODDING	SQ YD	2,772	2,772
28000510	INLET FILTERS	EACH	12	12
64100215	SIGHT SCREEN (WOODEN FENCE), TYPE S 6'	FOOT	1,773	1,773
67100100	MOBILIZATION	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
* 70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
* Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
Z0022800	FENCE REMOVAL	FOOT	1,360	1,360
XX005656	INLET FILTER CLEANING	EACH	48	48

\* INDICATES SPECIALTY ITEM

NOT FOR BIDDING

4/8/05 11/29/2005 11:47:03 AM I:\CCHL\041179\041179-gen.sht  
 COPYRIGHT © 2005 BY BAXTER & WOODMAN, INC.  
 ALL RIGHTS RESERVED. EXPIRES 4/30/2025

CONSULTANTS	REV. NO.	DATE	DESCRIPTION
	1	11/16/05	PER I.D.O.T. REVIEW
* REFER TO EQUIPMENT MANUFACTURER'S SHOP DRAWINGS			



**Baxter & Woodman**  
 Crystal Lake, Illinois 815.409.1360  
 Burlington, Wisconsin 262.763.7034  
 Mokena, Illinois 708.479.8090  
 DeKalb, Illinois 815.787.3111  
 Graylake, Illinois 815.893.5088  
 Rockford, Illinois 815.489.1661

**CITY OF COUNTRY CLUB HILLS, ILLINOIS**  
 CRAWFORD AVENUE & 167TH STREET  
 FENCE INSTALLATION

**STATE STANDARDS, INDEX OF SHEETS,  
 BENCHMARKS, SUMMARY OF QUANTITIES,  
 AND GENERAL NOTES**

DESIGNED BY	SCALE
MWP	NONE
DRAWN BY	PROJECT NO.
CJC	041179
CHECKED BY	SHEET NO.
NJP	
DATE	
09/30/05	<b>2 OF 6</b>

DRAWING FILE: ... \CCHL\041179\dgn\41179-gen.sht