

# SCHEDULES

PROJECT	SECTION	COUNTY	SHEETS	SHEET
245	98-2001-00-BR	BUREAU	65	7
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT - BR05-01(62)		

CONCRETE THRUST BLOCKS		
STATION	EACH	REMARKS
TOWNSHIP ROUTE 245		
TOWNSHIP		
L 12+63.98	1	
R 12+63.98	1	
<b>PROJECT TOTAL</b>	<b>2</b>	

60900515

WEATHERING STEEL TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT)		
STATION	EACH	REMARKS
TOWNSHIP ROUTE 245		
TOWNSHIP		
R 10+31.54 - 10+82.64	1	
L 10+84.14 - 11+16.98	1	
L 16+75.07 - 17+15.16	1	
<b>PROJECT TOTAL</b>	<b>3</b>	

63004011

TRAFFIC BARRIER TERMINAL, TYPE 5A (SPECIAL)		
STATION	EACH	REMARKS
TOWNSHIP ROUTE 245		
TOWNSHIP		
L 12+93.26 - 13+06.51	1	
R 12+93.26 - 13+06.51	1	
L 14+34.45 - 14+47.70	1	
R 14+34.45 - 14+47.70	1	
<b>PROJECT TOTAL</b>	<b>4</b>	

63100205

BARBED WIRE FENCE, FIVE STRAND		
STATION	FOOT	REMARKS
TOWNSHIP ROUTE 245		
TOWNSHIP		
L 14+75.16 - 15+35.50	60	
L 15+35.50 - 17+00	77	
L 17+00 - 18+67.41	158	
L 18+67.41 - 21+00	232	
L 21+00 - 22+50.83	152	
JOINT		
L 22+50.83 - 24+00	137	
L 24+00 - 25+57.04	145	
L 25+57.04 - 29+14.40	357	
EPPERSON ROAD		
CITY OF PRINCETON		
L 104+98.75 - 108+40	387	
L 108+40 - 108+40	15	
<b>PROJECT TOTAL</b>	<b>1,720</b>	

66503200

WEATHERING STEEL PLATE BEAM GUARD RAIL, SPECIAL		
STATION	FOOT	REMARKS
TOWNSHIP ROUTE 245		
TOWNSHIP		
15+16 RT - 15+20 RT	17.5	
<b>PROJECT TOTAL</b>	<b>17.5</b>	

FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS		
STATION	EACH	REMARKS
TOWNSHIP ROUTE 245		
TOWNSHIP		
23.24' L 5+50	1	
35' L 6+50	1	
35' L 8+27.19	1	
35' L 9+00	1	
35' L 10+00	1	
45' L 11+00	1	
55' L 11+95.06	1	
55' L 15+35.50	1	
55' L 17+00	1	
55' L 18+67.41	1	
55' L 21+00	1	
20.13' R 5+50	1	
28' R 5+50	1	
40' R 6+50	1	
43' R 9+00	1	
85.84' R 11+71.06	1	
94.13' R 14+25.05	1	
68.55' R 16+38.08	1	
49' R 18+25	1	
JOINT		
75' L 22+50.83	1	
75' L 24+00	1	
75' L 25+57.04	1	
75' R 29+14.40	1	
60' R 24+83	1	
54.92' R 25+17.42	1	
54.92' R 29+17.42	1	
EPPERSON ROAD		
CITY OF PRINCETON		
20.26' L 101+75	1	
40' L 101+75	1	
52.43' L 103+89.54	1	
49.69' R 101+77.01	1	
42.08' R 103+77.62	1	
36.10' R 105+84.12	1	
<b>PROJECT TOTAL</b>	<b>32</b>	

66600105

PAINT PAVEMENT MARKING - LINE 4"		
STATION	FOOT	REMARKS
TOWNSHIP ROUTE 245		
TOWNSHIP		
L 6+50 - 8+50	50	CL SKIP DASH YELLOW
R 6+50 - 12+76.48	626	CL SOLID YELLOW
L 6+50 - 12+76.48	626	EOP SOLID WHITE
R 6+50 - 12+76.48	626	EOP SOLID WHITE
L 8+50 - 12+76.48	426	CL SOLID YELLOW
L 14+64.48 - 22+50	786	CL SOLID YELLOW
R 14+64.48 - 15+50	86	CL SOLID YELLOW
L 14+64.48 - 22+50	786	EOP SOLID WHITE
R 14+64.48 - 22+50	786	EOP SOLID WHITE
R 15+50 - 22+50	176	CL SKIP DASH YELLOW
JOINT		
L 22+50 - 27+64.69	514	CL SOLID YELLOW
R 22+50 - 23+00	13	CL SKIP DASH YELLOW
L 22+50 - 29+30	680	EOP SOLID WHITE
R 22+50 - 29+30	680	EOP SOLID WHITE
R 23+00 - 27+64.69	464	CL SOLID YELLOW
CITY OF PRINCETON		
L 29+30 - 29+50	100	EOP SOLID WHITE
R 29+30 - 29+50	100	EOP SOLID WHITE
EPPERSON ROAD		
CITY OF PRINCETON		
L 102+00 - 104+07	207	CL SOLID YELLOW
R 102+00 - 104+07	207	CL SOLID YELLOW
L 105+11 - 107+85	274	CL SOLID YELLOW
R 105+11 - 107+85	274	CL SOLID YELLOW
L 102+00 - 103+45	145	EOP SOLID WHITE
L 105+34 - 107+85	251	EOP SOLID WHITE
R 102+00 - 107+85	585	EOP SOLID WHITE
<b>PROJECT TOTAL</b>	<b>9,467</b>	

78001110

PAINT PAVEMENT MARKING - LINE 8"		
STATION	FOOT	REMARKS
TOWNSHIP ROUTE 245		
CITY OF PRINCETON		
R 29+46.93 - 29+78	110	ISLAND OUTLINE (YEL)
<b>PROJECT TOTAL</b>	<b>110</b>	

78001140

PAINT PAVEMENT MARKING - LINE 12"		
STATION	FOOT	REMARKS
TOWNSHIP ROUTE 245		
JOINT		
27+64.69 - 29+30	45	DIAGONALS INSIDE MEDIAN (YEL)
CITY OF PRINCETON		
29+30 - 29+50	6	DIAGONALS INSIDE MEDIAN (YEL)
R 29+46.93 - 29+78	113	DIAGONALS INSIDE ISLAND (YEL)
<b>PROJECT TOTAL</b>	<b>164</b>	

78001150

PAINT PAVEMENT MARKING - LINE 24"		
STATION	FOOT	REMARKS
TOWNSHIP ROUTE 245		
CITY OF PRINCETON		
R 29+54.50	12	STOP BAR
R 29+37.75 - 29+54.50	22	STOP BAR
<b>PROJECT TOTAL</b>	<b>34</b>	

78001180

TERMINAL MARKER - DIRECT APPLIED		
STATION	EACH	REMARKS
TOWNSHIP ROUTE 245		
TOWNSHIP		
R 10+31.53	1	
L 10+64.14	1	
L 17+15.16	1	
<b>PROJECT TOTAL</b>	<b>3</b>	

78201000

SEEDLING-ACER SACCHARINUM		
STATION	UNIT	REMARKS
TOWNSHIP ROUTE 245		
TOWNSHIP		
6+50 - 22+50	6.51	SUGAR MAPLE, 2-YR OLD, BARE RT AS DIRECTED BY THE ENG
JOINT		
22+50 - 27+00	0.93	SUGAR MAPLE, 2-YR OLD, BARE RT AS DIRECTED BY THE ENG
<b>PROJECT TOTAL</b>	<b>7.44</b>	

F30020Y2

MODULAR BLOCK RETAINING WALL		
STATION	S.F.	REMARKS
TOWNSHIP ROUTE 245		
TOWNSHIP		
R 15+06 - 16+35	1,150	
<b>PROJECT TOTAL</b>	<b>1,150</b>	

XX000613

GUARDRAIL, SPECIAL		
STATION	FOOT	REMARKS
TOWNSHIP ROUTE 245		
TOWNSHIP		
R 10+82.64 - 12+93.26	212.5	
L 11+16.98 - 12+93.26	175	
R 14+47.70 - 15+16.45	68.8	
L 14+47.70 - 16+75.07	212.5	
<b>PROJECT TOTAL</b>	<b>668.8</b>	

XX006057

BREAKER-RUN CRUSHED STONE		
STATION	TONS	REMARKS
CONTINGENCY ITEM		
	1,640	AS DIRECTED BY THE ENGINEER
<b>PROJECT TOTAL</b>	<b>1,640</b>	

Z0005400

TIE BARS 3/4"		
STATION	EACH	REMARKS
TOWNSHIP ROUTE 245		
TOWNSHIP		
6+50 - 12+76.48	251	CENTERLINE
14+64.48 - 22+50	314	CENTERLINE
JOINT		
22+50 - 29+30	272	CENTERLINE
R 24+76.39 - 29+30	362	PAVEMENT TO SHOULDER TO GUTTER
L 29+26.95 - 29+30	2	PAVEMENT TO SHOULDER
CITY OF PRINCETON		
29+30 - 29+82	21	CENTERLINE
R 29+30 - 29+50	160	PAVEMENT TO SHOULDER TO GUTTER
L 29+30 - 29+50	80	PAVEMENT TO SHOULDER
CONTINGENCY	80	INTERSECTION (CONST. JOINTS) AS DIRECTED BY THE ENGINEER
EPPERSON ROAD		
CITY OF PRINCETON		
102+00 - 107+85	234	CENTERLINE
R 102+00 - 107+85	234	PAVEMENT TO SHOULDER
L 102+00 - 103+68.20	67	PAVEMENT TO SHOULDER
L 103+68.20 - 105+33.78	66	PAVEMENT TO SHOULDER
L 105+33.78 - 107+85	101	PAVEMENT TO SHOULDER
<b>PROJECT TOTAL</b>	<b>2244</b>	

Z0075310

GUARDRAIL, SPECIAL 2		
STATION	FOOT	REMARKS
TOWNSHIP ROUTE 245		
TOWNSHIP		
15+20 RT 63' - 16+36 RT 37'	132.5	
<b>PROJECT TOTAL</b>	<b>132.5</b>	

BRICK EMBOSSED, SPECIAL		
STATION	SQ YD	REMARKS
TOWNSHIP ROUTE 245		
TOWNSHIP		
12+58.98 - L 12+76.48	7	SHOULDER PAVEMENT
R 12+58.98 - R 12+76.48	7	SHOULDER PAVEMENT
L 14+64.48 - L 14+73.95	4	SHOULDER PAVEMENT
R 14+64.48 - R 14+73.95	4	SHOULDER PAVEMENT
12+76.48 - 13+06.48	111	APPROACH PAVEMENT
14+34.48 - 14+64.48	111	APPROACH PAVEMENT
<b>PROJECT TOTAL</b>	<b>244</b>	