CONTRACT NO. 94964

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
327	13B-1&13B-2	MARION	78	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			80% FED. 20% STATE	CONSTRUCTION TYPE CODE			
				DUMS CREEK		SKILLET FORK CREEK	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	X071-2A	SFTY-3N	X071-2A	SFTY-3N
20200100	EARTH EXCAVATION	CU YD	840	390		450	
20400800	FURNISHED EXCAVATION	CU YD	1555	1060		495	
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	291.9	118		173.9	
25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	1	0.6		0.4	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100	60		40	
28000300	TEMPORARY DITCH CHECKS	EACH	8	4		4	
28000400	PERIMETER EROSION BARRIER	FOOT	1800	1000		800	
28100107	STONE RIPRAP, CLASS A4	SQ YD	2655	1563		1092	
28200200	FILTER FABRIC	SQ YD	2655	1563		1092	
35650500	BASE COURSE WIDENING 10"	SQ YD	1309	692		617	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	549	326		223	
40600300	AGGREGATE (PRIME COAT)	TON	12	7		5	
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	400	160		240	
40600990	TEMPORARY RAMP	SQ YD	126	63		63	
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	546	273		273	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	110	55		55	
44000100	PAVEMENT REMOVAL	SQ YD	706	353		353	
44004250	PAVED SHOULDER REMOVAL	SQ YD	1193	640		553	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	51	38		13	
48202000	BITUMINOUS SHOULDERS SUPERPAVE	TON	633	378		255	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	2	1		1	
50200100	STRUCTURE EXCAVATION	CU YD	586.3	374		212.3	
50300100	FLOOR DRAINS	EACH	34	14		20	
50300225	CONCRETE STRUCTURES	CU YD	235.4	136		99.4	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	507.1	219.7		287.4	
50300260	BRIDGE DECK GROOVING	SQ YD	1538.4	654		884.4	
50300300	PROTECTIVE COAT	SQ YD	1874.4	818		1056.4	
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1	0.31		0.69	
50500505	STUD SHEAR CONNECTORS	EACH	6036	3012		3024	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	149,090	67270		81,820	
51201700	FURNISHING STEEL PILES HP12X74	FOOT	1218	1218			
51201710	FURNISHING STEEL PILES HP12X84	FOOT	1325			1325	

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

teasleyck
12/23/2005
c:\projects\94964d\d03502pa.dgn

PLOT DATE = 12/23/2005
FILE NAME = c:\projects\94964d\d03502pa.dgn
PLOT SCALE = 20.0000 ' / IN.
USER NAME = teasleyck